


PINE FOREST SEWER SYSTEM IMPROVEMENTS FOR THE CITY OF PORT WENTWORTH

OWNER
CITY OF PORT WENTWORTH
7224 GA HIGHWAY 21
PORT WENTWORTH, GA 31407
(912)-999-2084

24-HOUR CONTACT
OMAR SENATI-MARTINEZ
(912)-999-2084
OSENATIMARTINEZ@
CITYOFPORWENTWORTH.COM

CIVIL ENGINEERING PLANS
SHEET C1.1 –
SHEET C1.2 –
SHEET C2.1 –
SHEET C5.1 THRU C5.5
SHEET C7.1 –
SHEET C7.2 –
SHEET C7.3 –
SHEET C7.4 – C7.5
SHEET C7.6 THRU C7.7
SHEET C8.1

TITLE SHEET
GENERAL NOTES
EXISTING CONDITIONS
SEWER PLAN & PROFILE
INITIAL EROSION CONTROL PLAN
INTERMEDIATE EROSION CONTROL PLAN
FINAL EROSION CONTROL PLAN
EROSION CONTROL NOTES
EROSION CONTROL DETAILS
SITE DETAILS



BEGINNING: N32° 12' 11.16", W81° 11' 54.39"
END: N32° 12' 5.52", W81° 11' 34.36"
DISTURBED ACREAGE: 1.81 AC.
TOTAL SITE ACREAGE: 1.81 AC.

ENGINEER
T. R. LONG ENGINEERING, P.C.
114 NORTH COMMERCE STREET
HINESVILLE, GEORGIA 31313
(912) 368-5664

DRAWING LEGEND		
DESCRIPTION	PROPOSED	EXISTING
RIGHT OF WAY	--- R/W	--- R/W
EDGE OF PAVEMENT	---	---
DITCH CENTERLINE	- . - . - .	- . - . - .
SANITARY SEWER	8"S	---
WATER LINE	10"W	--- 10"W ---
FORCE MAIN	FM	--- FM ---
UNDERGROUND GAS LINE	8"G	--- 8"G ---
CONTOURS	81	--- 81 ---
STORM DRAINAGE PIPE	---	==
ELEVATION	FG: 78.15	X 81.90
SILT FENCE NON-SENSITIVE	Sd1-NS	
SILT FENCE SENSITIVE	Sd1-S	
INLET PROTECTION	Sd2-P	
CHECK DAM- HAY BALE	Cd-Hb	
CHECK DAM - RIP RAP	Cd-Rp	
CONSTRUCTION EXIT	Co	
STORM OUTLET PROTECTION	St	
SILT FENCE	---	
MULCHING	Ds1	
TEMPORARY GRASSING	Ds2	
PERMANENT GRASSING	Ds3	
FIRE HYDRANT		
SEWER MANHOLE		
WATER VALVE		
DRAINAGE FLOW		
WATER METER		
BENCHMARK		
WELL		
GUY POLE		
IRON PIN	SET I.P.S	FOUND I.P.F
TELEPHONE PEDESTAL		
POWER POLE		

THIS DRAWING IS THE PROPERTY OF T. R. LONG ENGINEERING, P.C. AND MAY NOT BE REPRODUCED, COPIED, OR USED IN ANY MANNER WITHOUT THE WRITTEN PERMISSION OF T. R. LONG ENGINEERING, P.C.

THE CONTRACTOR SHALL VERIFY ALL DIMENSIONS CONTAINED WITHIN THIS SET OF DOCUMENTS AND SHALL REPORT ANY DISCREPANCIES TO T. R. LONG ENGINEERING, P.C. FOR IMMEDIATE RESOLUTION.

CSWC# 000002134

HINESVILLE:
114 North Commerce Street
Hinesville, Georgia 31313
(912) 368-5664

SAVANNAH:
308 Commerce Drive
Savannah, Georgia 31406
(912) 335-1046

www.trlongeng.com

PINE FOREST
SEWER SYSTEM IMPROVEMENTS
CITY OF PORT WENTWORTH

SHEET NAME:
TITLE SHEET

REVISIONS:

1.	
2.	
3.	
4.	
5.	
6.	
7.	
8.	
9.	
10.	

INITIAL DATE: 6/22/2022
DRAWN BY: KRC
CHECKED BY: TRL
PROJECT #: 2021-285

SHEET NUMBER:
C.I.1

Paving Notes

1. All work shall comply with all applicable codes, regulations, and/or local standards imposed by local utility, city, county, and state. It is the contractor's responsibility that all the construction be in accordance with the City of Port Wentworth and GDOT standard details and specifications.
2. Contractor shall comply with all pertinent provisions of the "Manual of Accident Prevention in Construction" issued by AGC of American Inc., and the safety and health regulations for construction issued by the U.S. Department of Labor.
3. Contractor shall provide all necessary barricades, sufficient lights, signs and other traffic control methods as may be necessary for the protection and safety of the public and shall be provided and maintained throughout all construction adjacent to and within all roadways. Contractor shall submit traffic control plan to city for approval.
4. The contractor shall take necessary measures to separate work areas from pedestrian traffic and to insure safe pedestrian passage at all times.
5. All signs, pavement markings, and other traffic control devices shall conform to the Manual of Uniform Traffic Control Devices. A minimum clearance of two feet shall be maintained between the face of curb and any part of a traffic sign or light pole. Contractor shall coordinate installation of all signs, pavement markings, and other traffic control devices with other contractors on signs or light poles.
6. Contractor shall saw-cut to provide smooth transitions at tie-ins to existing edges of pavement and at cold joints of recently paved asphalt.
7. Joints or score marks are to be sharp and clean without showing edges of jointing tool.
8. Contractor shall saw-cut tie-ins at existing curbs as necessary to ensure smooth transitions, contractor shall saw-cut and transition to meet existing pavement as necessary and as directed by inspector to insure positive drainage. (Typical at all intersections)
9. Paving contractor shall install paper breakaway edges at cold joints or saw-cut as required to insure a straight, full-depth joint face immediately prior to installing abutting hot asphalt.
10. All dimensions are to back of curb unless indicated otherwise.
11. Contractor shall be responsible for cost of pavement replacement where utility lines are extended across existing asphalt.
12. Asphalt surface course shall be laid with the direction of traffic in all drive lanes within parking fields.
13. Base and asphalt thickness are minimum required. Refer to specifications for type of paving and base to be used.
14. All concrete shall be Class A 4000 P.S.I. unless noted otherwise. Do not pour any concrete before forms are inspected and approved by the Inspector.
15. All ramps constructed are not to exceed a slope of 1:12. All sidewalks shall not have a cross-slope greater than 1:50
16. Concrete dumpster pads to be flush with pavement unless indicated otherwise.
17. See Detail sheets for additional details on striping, signs, etc.

Inspection notes


1. Each day when any type of construction activity has taken place at a primary permittee's site, certified personnel provided by the primary permitte shall inspect: (a) all areas at the primary permittee's site where petroleum products are stored, used, or handled for spills and leaks from vehicles and equipment and (b) all locations at the primary permittee's site where vehicles enter or exit the site for evidence of off-site sediment tracking. These inspections must be conducted until a notice of termination is submitted.
2. Measure and record rainfall within disturbed areas of the site that have not met final stabilization once every 24 hours except any non-working saturday, non-working sunday and non-working federal holiday. The data collected for the purpose of compliance with this permit shall be representative of the monitored activity. Measurement of rainfall may be suspended if all areas of the site have undergone final stabilization or established a crop of annual vegetation and a seeding of target perennials appropriate for the region.
3. Certified personnel (provided by the primary permittee) shall inspect the following at least once every seven (7) calendar days and within 24 hours of the end of a storm that is 0.5 inches rainfall or greater (unless such storm ends after 5:00 pm on any friday or on any non-working saturday, non-working sunday or any non-working federal holiday in which case the inspection shall be completed by the end of the next business day and/or working day, whichever occurs first): (a) disturbed areas of the primary permittee's construction site; (b) areas used by the primary permittee for storage of materials that are exposed to precipitation; and (c) structural control measures. Erosion and sediment control measures identified in the plan applicable to the primary permittee's site shall be observed to ensure that they are operating correctly. Where discharge locations or points are accessible, they shall be inspected to ascertain whether erosion control measures are effective in preventing significant impacts to receiving water(s). For areas of a site that have undergone final stabilization or established a crop of annual vegetation and a seeding of target perennials appropriate for the region, the permittee must comply with part iv.d.4.a.(4). These inspections must be conducted until a notice of termination is submitted.
4. Certified personnel (provided by the primary permittee) shall inspected at least once per month during the term of this permit (i.e., until a notice of termination has been submitted) the areas of the site that have undergone final stabilization or established a crop of annual vegetation and a seeding target perennials appropriate for the region. These areas shall be inspected for evidence of, or the potential for, pollutants entering the drainage system and the receiving water(s). Erosion and sediment control measures identified in the plan shall be observed to ensure that they are operating correctly. Where discharge locations or points are accessible, they shall be inspected to ascertain whether erosion control measures are effective in preventing significant impacts to receiving water(s).
5. Based on the results of each inspection, the site description and the pollution prevention and control measures identified in the erosion, sedimentation and pollution control plan, the plan shall be revised as appropriate not later than seven (7) calendar days following each inspection. Implementation of such changes shall be made as soon as practical but in no case later than seven (7) calendar days following each inspection.
6. A report of each inspection that includes the name(s) of certified personnel making each inspection, the date(s) of each inspection, construction phase (i.e., initial, intermediate or final), major observations relating to the implementation of the erosion, sedimentation and pollution control plan and actions taken in accordance with part iv.d.4.a.(5) of the permit shall be made and retained at the site or be readily available at a designated alternate location until the entire site or that portion of a construction project that has been phased has undergone final stabilization and a notice of termination is submitted to epd. Such reports shall be readily available by end of the second business day and/or working day and shall identify all incidents of best management practices that have been properly installed and/or maintained as described in the plan. Where the report does not identify any incidents, the inspection report shall contain a certification that the best management practices are in compliance with the erosion, sedimentation and pollution control plan. The report shall be signed in accordance with part v.g.2. Of this permit

Site Grading Notes

1. Dimensions on buildings are for grading purposes only and are not to be used to lay-out footings. Refer to Structural Drawings for foundation information.
2. Grading contractor shall notify and cooperate with all utility companies or firms having facilities on or adjacent to the site before disturbing, altering, removing, relocating, adjusting or connecting to said facilities. Contractor shall pay all costs in connection with the alteration or or relocation of the facilities. Contractors shall raise or lower tops of existing manholes to remain as required to match finished grades.
3. Grading contractor shall cooperate and work with all other contractors performing work on this project to insure proper and timely completion of this project.
4. The grading contractor shall use whatever measures are required to prevent silt and construction debris from flowing onto adjacent properties. Contractor shall comply with all local erosion, conservation, and siltation ordinances. Contractors shall remove all temporary erosion control structures upon completion of permanent drainage facilities and not before the establishment of a stand of grass sufficient to prevent erosion.
5. For any work on the state or city right-of-way, the grading contractor shall:
 - A. Not store material, excess dirt, or equipment in the right-of-way. The pavement shall be kept free from any mud or excavation waste from trucks or other equipment. On completion of the work, all excess material shall be removed from the right-of-way.
 - B. Provide all necessary and adequate safety precautions such as signs, flags, light barricades, and flag-men as required by the local authorities and in accordance with solely responsible for and hold harmless the City, State, Architect, Engineer, and Owner from any claims for damage done to existing private property, public utilities, or to the traveling public.
 - C. Complete work to the satisfaction of the City Public Works Department and obtain a letter from the Department stating that the work is acceptable.
7. Grading contractor shall take all available precautions to control dust. Contractor shall control dust by sprinkling, or by other methods as directed by Engineer and/or Owner's representative, at no additional cost to Owner.
8. Site grading contractor shall terminate all storm drain pipes five feet maximum from building unless otherwise noted.
9. Storm sewer lead-ins to building shall not be installed until building plans are completed and locations established on the architectural plans. Lead-ins may change 15' horizontally and 3' vertically prior to installation at no additional cost to the owner. Contractor shall request and receive written approval from prime contractor prior to installation of lead-ins. Contractor shall coordinate locations, size, and invert elevations of storm sewers with approved building plumbing plans.
10. All excavating is unclassified and shall include all materials encountered.
11. Before any machine work is done, contractor shall stake out and mark the items established by the site plan, control points shall be preserved at all times during the course of the project. Lack of proper working points and grade stakes may require satisfaction owner must approved staked items prior to construction.
12. Temporary erosion control devices to be installed prior to beginning of grading. Contractor shall maintain all temporary erosion control devices and shall remove silt contractor at least once a week.
13. Contractor to coordinate all work with other utility installations not covered in these plans, (Electric, Telephone, Gas, Cable, Etc.) and allow for their operations and construction to be performed.
14. Cut and fill slopes are not to exceed 3:1 unless otherwise noted.
15. In no case shall any paved areas be less than a slope of 1.0%. All accessible sidewalks and aisle slopes not to exceed 2% cross-slope.
16. Contractor shall repair or replace in-kind any damage that occurs as result of his work.
17. All linear footage for all utility pipes are approximate, actual installed quantities may vary.
18. Grading contractor shall restore to grade and compaction all areas disturbed by building construction prior to base and paving operations commencing.
19. Grading contractor shall maintain all weather construction access roads as required by general contractor.

Site Utility Notes

1. The site utility plan is for sanitary sewer and water line construction only. Do not use for grading or storm sewer construction.
2. All pipe lengths are horizontal distances and are approximate.
3. All domestic water and sanitary sewer stubs to be terminated 5 feet outside of the building unless otherwise noted. The end of these service lines shall be tightly plugged or capped and marked until such time as connection is made inside building by plumbing contractor.
4. Site utility contractor shall provide all the materials and appurtenances necessary for the complete installation of the utilities. All pipe and fittings shall be inspected by the Water Department Inspector prior to being covered. The inspector must also be present during pressure testing and disinfection of laterals and his signature of approval is required.
5. All work shall comply with all applicable codes, regulations, and/or local standards imposed by local utility and City of Port Wentworth.
6. The site utility contractor shall make arrangements with the local utility authorities for connection to the existing mains and pay all applicable fees.
7. All water lines shall have a minimum cover of 36" above top of pipe.
8. Contractor shall adjust location of proposed water lines as required to avoid conflicts with storm sewer or other utilities at no extra cost.
9. Based on the current edition of the international plumbing code, cleanouts are required at a maximum spacing of 100 feet on utility lead-ins to building. Contractor to provide a cleanout within 5 feet of building and at all bends.
10. The site utility contractor shall cooperate and work with all other contractors on the site.
11. All materials shall be U.L. listed and approved by the local utility company unless directed otherwise by the Engineer.
12. The existing utility facilities and locations shown on the drawings are taken from readily available information. The actual locations of the utility facilities may vary somewhat from the locations shown or indicated on the drawings. The site utility contractor shall contact all agencies with utility facilities in the vicinity of the work and shall locate all underground facilities before beginning work. The contractor shall project all utility facilities and repair any damages resulting from their work, in conformance with the contract documents and specifications and relocate if required.
13. All sanitary sewer pipe shall be SDR-26 meeting ASTM D3034 with gasket type joints meeting ASTM F477.
14. Utility lead-ins to building shall not be installed until building plans are completed and locations established on the architectural plumbing plans. Lead-ins my change 15' horizontally and 3' vertically prior to installations at no additional cost to the owner. Utility contractor shall request and receive written approval from prime contractor prior to installation of lead-ins. Location, size and invert elevations of sanitary sewer shall be coordinated with the approved plumbing plans for the building.
15. Building plumbing contractor shall pay all cost for water meters, meter boxes, valves, etc. to provide a complete job per local authority requirements.
16. Thrust blocks shall be provided at all tees, elbows, and bends of sufficient size to comply with minimum standards of N.F.P.A. – Existing soil conditions.
17. Should latent soil conditions necessitate, contractor shall install special supports for piping and/or appurtenances including the removal of unsuitable material and backfilling with gravel or other material. Contractor shall perform any such work as directed by the civil engineer and/or soils engineer at no cost to owner.
18. Contractor to coordinate all work with other utility installations not covered in these plans (Electric, Telephone, Gas, Cable, etc.) and allow for their operations and construction to be prepared.
19. The site utility contractor shall coordinate and pay for all sanitary sewer connections. Sanitary sewer connection final tie-in to the existing manhole(s) shall not be made until completion of the proposed system and all manholes have been brought above ground to insure sediment does not enter system. Lines shall be properly cleaned, if needed.
20. Site utility contractor to coordinate with irrigation contractor to provide power in conduit to irrigation controller per manufacturers recommendations. Verify exact location of controller with owner prior to installation.



THIS DRAWING IS THE PROPERTY OF T. R. LONG ENGINEERING, P.C. AND MAY NOT BE REPRODUCED, COPIED, OR TRANSMITTED IN ANY MANNER WITHOUT THE WRITTEN PERMISSION OF T. R. LONG ENGINEERING, P.C. THE CONTRACTOR SHALL VERIFY ALL DIMENSIONS CONTAINED WITHIN THIS SET OF DOCUMENTS AND SHALL REPORT ANY DISCREPANCIES TO T. R. LONG ENGINEERING, P.C. FOR IMMEDIATE RESOLUTION.

HINESVILLE:
114 North Commerce Street
Hinesville, Georgia 31513
(912) 368-5664
SAVANNAH:
308 Commercial Drive
Savannah, Georgia 31406
(912) 335-1046



PINE FOREST
SEWER SYSTEM IMPROVEMENTS
CITY OF PORT WENTWORTH

SHEET NAME:
GENERAL
NOTES



REVISIONS:

- | |
|----|
| 1. |
| 2. |
| 3. |
| 4. |
| 5. |
| 6. |
| 7. |
| 8. |
| 9. |
| 10 |

INITIAL DATE: 6/22/2022
DRAWN BY: RRC
CHECKED BY: TRL
PROJECT #: 2021-285

SHEET NUMBER:

CI.2



THIS DRAWING IS THE PROPERTY OF T. R. LONG ENGINEERING, P.C. AND MAY NOT BE REPRODUCED OR TRANSMITTED IN ANY FORM OR BY ANY MEANS, WITHOUT THE WRITTEN PERMISSION OF T. R. LONG ENGINEERING, P.C.

THE CONTRACTOR SHALL VERIFY ALL DIMENSIONS CONTAINED WITHIN THIS SET OF DOCUMENTS AND SHALL REPORT ANY DISCREPANCIES TO T. R. LONG ENGINEERING, P.C. FOR IMMEDIATE RESOLUTION.

CSWCC# 0000020134

HINESVILLE:
114 North Commerce Street
Hinesville, Georgia 31313
(912) 368-5664

SAVANNAH:
308 Commercial Drive
Savannah, Georgia 31406
(912) 335-1046

TR LONG
ENGINEERING, P.C.

www.trlongeng.com

**PINE FOREST
SEWER SYSTEM IMPROVEMENTS
CITY OF PORT WENTWORTH**


SHEET NAME:
EXISTING
CONDITIONS

REVISIONS:



1.	
2.	
3.	
4.	
5.	
6.	
7.	
8.	
9.	
10.	

INITIAL DATE: 6/22/2022
DRAWN BY: KRC
CHECKED BY: TRL
PROJECT #: 2021-285

SHEET NUMBER:
C2.I



- NOTES:
1. CONTRACTOR TO LOCATE EXISTING LATERALS FROM RESIDENTS.
 2. CONTRACTOR TO CONNECT EXISTING LATERALS TO NEW 8" PVC MAIN ONCE LINE IS ACTIVE.
 3. CONNECTIONS TO NEW 8" PVC MAIN THROUGH 8X4 WYE. CONTRACTOR TO ABANDON EXISTING SEWER SYSTEM AFTER NEW SYSTEM IS OPERATIONAL/COMPLETE.
 4. CONTRACTOR TO REMOVE/DISPOSE OF MANHOLE TOP SECTIONS TO A DEPTH OF 4', FILL EXISTING MANHOLES/SYSTEM WITH SAND.



THIS DRAWING IS THE PROPERTY OF T. R. LONG ENGINEERING, P.C. AND MAY NOT BE REPRODUCED, COPIED, OR TRANSMITTED IN ANY MANNER WITHOUT THE WRITTEN PERMISSION OF T. R. LONG ENGINEERING, P.C.

THE CONTRACTOR SHALL VERIFY ALL DIMENSIONS CONTAINED WITHIN THIS SET OF DOCUMENTS AND SHALL REPORT ANY DISCREPANCIES TO T. R. LONG ENGINEERING, P.C. FOR IMMEDIATE RESOLUTION.

CSWCC# 000002134

HINESVILLE:
114 North Commerce Street
Hinesville, Georgia 31313
(912) 368-5664

SAVANNAH:
308 Commerce Drive
Savannah, Georgia 31406
(912) 335-1046

www.trlongeng.com

TRLONG
ENGINEERING, P.C.

PINE FOREST
SEWER SYSTEM IMPROVEMENTS
CITY OF PORT WENTWORTH



SHEET NAME:
SEWER PLAN &
PROFILE



REVISIONS:

1.	
2.	
3.	
4.	
5.	
6.	
7.	
8.	
9.	
10.	


INITIAL DATE: 6/22/2022
DRAWN BY: KRC
CHECKED BY: TRL
PROJECT #: 2021-285

SHEET NUMBER:
C5.I





- NOTES:
1. CONTRACTOR TO LOCATE EXISTING LATERALS FROM RESIDENTS.
 2. CONTRACTOR TO CONNECT EXISTING LATERALS TO NEW 8" PVC MAIN ONCE LINE IS ACTIVE.
 3. CONNECTIONS TO NEW 8" PVC MAIN THROUGH 8X4 WYE.
 4. CONTRACTOR TO ABANDON EXISTING SEWER SYSTEM AFTER NEW SYSTEM IS OPERATIONAL/COMPLETE. CONTRACTOR TO REMOVE/DISPOSE OF MANHOLE TOP SECTIONS TO A DEPTH OF 4', FILL EXISTING MANHOLES/SYSTEM WITH SAND.



THIS DRAWING IS THE PROPERTY OF T. R. LONG ENGINEERING, P.C. AND MAY NOT BE REPRODUCED, COPIED, OR USED IN ANY MANNER WITHOUT THE EXPRESS WRITTEN PERMISSION OF T. R. LONG ENGINEERING, P.C.

THE CONTRACTOR SHALL VERIFY ALL DIMENSIONS CONTAINED WITHIN THIS SET OF DOCUMENTS AND SHALL REPORT ANY DISCREPANCIES TO T. R. LONG ENGINEERING, P.C. FOR IMMEDIATE RESOLUTION.

GSWC# 000002134

HINESVILLE:
114 North Commerce Street
Hinesville, Georgia 31313
(912) 368-5664

SAVANNAH:
308 Commercial Drive
Savannah, Georgia 31406
(912) 335-1046

TR LONG
ENGINEERING, P.C.

www.trlongeng.com



PINE FOREST
SEWER SYSTEM IMPROVEMENTS
CITY OF PORT WENTWORTH

SHEET NAME:
SEWER PLAN &
PROFILE

REVISIONS:
1.
2.
3.
4.
5.
6.
7.
8.
9.
10.


INITIAL DATE: 6/22/2022
DRAWN BY: KRC
CHECKED BY: TRL
PROJECT #: 2021-285

SHEET NUMBER:
C5.4




WET WELL SECTION A-A

NOT TO SCALE




PLAN VIEW

NOT TO SCALE



NOT IN CONTRACT
BY OTHERS



GRAPHIC SCALE

(IN FEET)
1 inch = 5 ft.

WETWELL DESIGN SCHEDULE

DESCRIPTION	ELEVATION
FRAME	12.36
H.W.L. ALARM	-5.02
LAG ON	-5.52
LEAD ON	-6.02
L.W.L. PUMPS OFF	-7.54
BOTTOM	-9.54
WETWELL DIA.	6'-0"

PUMP STATION DESIGN SCHEDULE

DESCRIPTION	INITIAL
NO. OF PUMPS	2
RPM	3495
PHASE	3
VOLTAGE	230
MIN. HP	17
MIN. PUMPING RATE	209 GPM
TDH	139.0'

NOTE:
PUMPS SHALL BE EQUIVALENT TO FLYGT
MODEL NP-3153 SH 3-275 WITH A 167MM
IMPELLER DIAMETER. NO OTHER PUMPS SHALL
BE USED UNLESS ACCEPTED BY ENGINEER.

CONTRACTOR TO COMPLETELY DEMO WET WELL OF ALL
EXISTING EQUIPMENT. EXISTING CONTROLS AND PUMPS TO BE
DELIVERED TO THE CITY OF PORT WENTWORTH PUBLIC WORKS
DEPARTMENT. CONTRACTOR TO INSTALL BASE ELBOWS,
ALL VERTICAL PIPING, GUIDE RAILS, ANCHOR SYSTEMS, PUMPS,
ELECTRICAL, CONTROLS, CONTROL PANEL AND ALL ITEMS
REQUIRED FOR THE COMPLETE REHABILITATION OF THE PUMP
STATION BACK TO OPERATIONAL CONDITION.

THE CONTRACTOR IS RESPONSIBLE FOR THE FULL OPERATION
OF THE STATION INCLUDING PROVIDING, OPERATING,
MAINTAINING, AND REPAIRING THE BYPASS SYSTEM 24 HOURS
A DAY 7 DAYS A WEEK THROUGHOUT THE ENTIRE DURATION
OF THE PROJECT VIA ATTENDED OPERATION OR APPROVED
EQUIVALENT. THE CONTRACTOR OR QUALIFIED REPRESENTATIVE
MUST REPORT TO THE STATION WITHIN 15 MINUTES OF ANY
ALARM OR MALFUNCTION AND COMMENCE WITH THE
NECESSARY CORRECTIVE ACTIONS TO PROVIDE CONTINUOUS
AND RELIABLE OPERATION OF THE STATION INCLUDING THE
BYPASS SYSTEM.



THIS DRAWING IS THE PROPERTY OF T. R. LONG
ENGINEERING, P.C. AND MAY NOT
REPRODUCE, EITHER IN PART OR WHOLLY, IN
ANY MANNER WITHOUT THE EXPRESS WRITTEN
PERMISSION OF T. R. LONG ENGINEERING, P.C.
THE CONTRACTOR SHALL VERIFY ALL DIMENSIONS
CONTAINED WITHIN THIS SET OF DOCUMENTS AND
SHALL REPORT ANY DISCREPANCIES TO T. R.
LONG ENGINEERING, P.C. FOR IMMEDIATE
RESOLUTION.

CSWC# 000002134

HINESVILLE:
114 North Commerce Street
Hinesville, Georgia 31313
(912) 368-5664
SAVANNAH:
308 Commercial Drive
Savannah, Georgia 31406
(912) 335-1046

TRLONG
ENGINEERING, P.C.

www.trlongeng.com

PINE FOREST
SEWER SYSTEM IMPROVEMENTS
CITY OF PORT WENTWORTH



SHEET NAME:
PUMP STATION
DETAILS

REVISIONS:
1.
2.
3.
4.
5.
6.
7.
8.
9.
10.

INITIAL DATE: 6/22/2022
DRAWN BY: KRC
CHECKED BY: TRL
PROJECT #: 2021-285

SHEET NUMBER:

C5.6



THIS DRAWING IS THE PROPERTY OF T. R. LONG ENGINEERING, P.C. AND MAY NOT BE REPRODUCED, COPIED, OR TRANSMITTED IN ANY MANNER WITHOUT THE WRITTEN PERMISSION OF T. R. LONG ENGINEERING, P.C.

THE CONTRACTOR SHALL VERIFY ALL DIMENSIONS CONTAINED WITHIN THIS SET OF DOCUMENTS AND SHALL REPORT ANY DISCREPANCIES TO T. R. LONG ENGINEERING, P.C. FOR IMMEDIATE RESOLUTION.

HINESVILLE:
114 North Commerce Street
Hinesville, Georgia 31313
(912) 368-5664

SAVANNAH:
308 Commercial Drive
Savannah, Georgia 31406
(912) 335-1046

www.trlongeng.com

TRLONG
ENGINEERING, P.C.

**PINE FOREST
SEWER SYSTEM IMPROVEMENTS
CITY OF PORT WENTWORTH**



SHEET NAME:
INITIAL EROSION
CONTROL PLAN

REVISIONS:

1.	
2.	
3.	
4.	
5.	
6.	
7.	
8.	
9.	
10.	

INITIAL DATE: 6/22/2022
DRAWN BY: RRC
CHECKED BY: TRL
PROJECT #: 2021-285

SHEET NUMBER:
C7.I



THIS DRAWING IS THE PROPERTY OF T. R. LONG ENGINEERING, P.C. AND MAY NOT BE REPRODUCED, COPIED, OR TRANSMITTED IN ANY MANNER WITHOUT THE WRITTEN PERMISSION OF T. R. LONG ENGINEERING, P.C. THE CONTRACTOR SHALL VERIFY ALL DIMENSIONS CONTAINED WITHIN THIS SET OF DOCUMENTS AND SHALL REPORT ANY DISCREPANCIES TO T. R. LONG ENGINEERING, P.C. FOR IMMEDIATE RESOLUTION.

GSWCC# 0000002134

HINESVILLE:
114 North Commerce Street
Hinesville, Georgia 31313
(912) 368-5664

SAVANNAH:
308 Commercial Drive
Savannah, Georgia 31406
(912) 335-1046

TR LONG
ENGINEERING, P.C.

www.trlongeng.com

**PINE FOREST
SEWER SYSTEM IMPROVEMENTS
CITY OF PORT WENTWORTH**

SHEET NAME:
INTERMEDIATE
EROSION CONTROL
PLAN

REVISIONS:

1.	
2.	
3.	
4.	
5.	
6.	
7.	
8.	
9.	
10.	

INITIAL DATE: 6/22/2022
DRAWN BY: RRC
CHECKED BY: TRL
PROJECT #: 2021-285

SHEET NUMBER:
C7.2

PROJECT INFORMATION

PROJECT TITLE:

PINE FOREST SEWER SYSTEM IMPROVEMENTS

OWNER:

CITY OF PORT WENTWORTH
7224 GA HIGHWAY 21
PORT WENTWORTH, GA 31407

(912)-999-2084

24 HOUR CONTACT:

OMAR SENATI-MARTINEZ

(912)-999-2084

ENGINEER:

OSENATIMARTINEZ@CITYOFPORTWENTWORTH.COM

ENGINEER:

T.R. LONG ENGINEERING, P.C.
114 NORTH COMMERCE ST.
HINESVILLE, GEORGIA 31313
(912) 368-5664

GOVERNING AUTHORITY:

CITY OF PORT WENTWORTH
7224 GA-21
PORT WENTWORTH, GA 31407
912-964-4379

EROSION, SEDIMENTATION & POLLUTION CONTROL PLAN CHECKLIST
INFRASTRUCTURE CONSTRUCTION PROJECTS

SWCD: COASTAL GEORGIA
PROJECT NAME: PINE FOREST SEWER SYSTEM IMPROVEMENTS ADDRESS: PINE FOREST S/D
CITY/COUNTY: CITY OF PORT WENTWORTH DATE ON PLANS: 6/22/2022
NAME & EMAIL OF PERSON FILLING OUT CHECKLIST: KEITH CAUSEWAY, kcauseway@trlongeng.com

EROSION, SEDIMENT, & POLLUTION CONTROL PLAN CHECKLIST

1. REQUIREMENT: THE APPLICABLE EROSION, SEDIMENTATION AND POLLUTION CONTROL PLAN CHECKLIST ESTABLISHED BY THE COMMISSION AS OF JANUARY 1 OF THE YEAR IN WHICH THE LAND-DISTURBING ACTIVITY WAS PERMITTED.

RESPONSE: THE 2022 EROSION, SEDIMENT AND POLLUTION CONTROL PLAN CHECKLIST FOR INFRASTRUCTURE WAS USED FOR THIS PROJECT.
2. REQUIREMENT: LEVEL II CERTIFICATION NUMBER ISSUED BY THE COMMISSION, SIGNATURE AND SEAL OF THE CERTIFIED DESIGN PROFESSIONAL.

RESPONSE: THE LEVEL II CERTIFICATION NUMBER ISSUED BY THE COMMISSION, SIGNATURE AND SEAL OF THE CERTIFIED DESIGN PROFESSIONAL IS FOUND ON THE UPPER RIGHT HAND SIDE OF ALL SHEETS.
3. REQUIREMENT: THE NAME AND PHONE NUMBER OF THE 24-HOUR LOCAL CONTACT RESPONSIBLE FOR EROSION, SEDIMENTATION AND POLLUTION CONTROLS.

RESPONSE: THE NAME AND PHONE NUMBER OF THE 24-HOUR LOCAL CONTACT IS SHOWN IN THE ABOVE "PROJECT INFORMATION" SECTION.
4. REQUIREMENT: PROVIDE THE NAME, ADDRESS, EMAIL ADDRESS AND PHONE NUMBER OF THE PRIMARY PERMITTEE.

RESPONSE: THE NAME, ADDRESS AND PHONE NUMBER OF THE PRIMARY PERMITTEE IS SHOWN ABOVE ON THE "PROJECT INFORMATION" SECTION.
5. REQUIREMENT: NOTE TOTAL AND DISTURBED ACREAGE OF THE PROJECT OR PHASE UNDER CONSTRUCTION.

RESPONSE: THE TOTAL ACREAGE OF THE SITE IS 1.81 AND THE DISTURBED ACREAGE IS 1.81
6. REQUIREMENT: PROVIDE THE GPS LOCATIONS OF THE BEGINNING AND END OF THE INFRASTRUCTURE PROJECT. GIVE THE LATITUDE AND LONGITUDE IN DECIMAL DEGREES.

RESPONSE: THE GPS LOCATIONS OF THE BEGINNING OF THE PROJECT IS 32.203140°, -81.198537° AND END OF THE PROJECT IS 32.201530°, -81.192883° .
7. REQUIREMENT: INITIAL DATE OF THE PLAN AND THE DATES OF ANY REVISIONS MADE TO THE PLAN INCLUDING THE ENTITY WHO REQUESTED THE REVISIONS.

RESPONSE: THE INITIAL DATE AND ANY REVISIONS ARE ON THE BOTTOM RIGHT SIDE OF ALL SHEETS
8. REQUIREMENT: DESCRIPTION OF THE NATURE OF CONSTRUCTION ACTIVITY AND EXISTING SITE CONDITIONS..

RESPONSE: THE PROJECT CONSIST OF IMPROVEMENTS TO THE EXISTING SEWER SYSTEM AND REHABILITATION OF THE SEWER PUMP STATION.
9. REQUIREMENT: PROVIDE VICINITY MAP SHOWING SITE'S RELATION TO SURROUNDING AREAS. INCLUDE DESIGNATION OF SPECIFIC PHASE, IF NECESSARY.

RESPONSE: A VICINITY MAP IS SHOWN ON THE TITLE SHEET OF THESE PLANS.
10. REQUIREMENT: IDENTIFY THE PROJECT RECEIVING WATERS AND DESCRIBE ALL SENSITIVE ADJACENT AREAS INCLUDING STREAMS, LAKES, RESIDENTIAL AREAS, WETLANDS, ETC. WHICH MAY BE AFFECTED.

RESPONSE: THE SITE CURRENTLY DRAINS TO DRAINAGE DITCHES LOCATED IN THE RIGHT OF WAY OF JERICO DRIVE AND LIMERICK ROAD. THESE DITCHES THEN DISCHARGE TO LAKE GEORGE THAT ULTIMATELY DISCHARGES TO THE JERICO RIVER. THE PROPOSED SITE'S DRAINAGE PATTERN WILL REMAIN THE SAME AND WILL CONTINUE TO DISCHARGE STORMWATER TO LAKE GEORGE.
11. REQUIREMENT: DESIGN PROFESSIONAL'S CERTIFICATION STATEMENT AND SIGNATURE THAT THE SITE WAS VISITED PRIOR TO DEVELOPMENT OF THE ES&PC PLAN AS STATED ON PART IV PAGE 21 OF THE PERMIT.

RESPONSE: PLEASE SEE THE DESIGN PROFESSIONAL'S CERTIFICATION SECTION ON THIS SHEET.
12. REQUIREMENT: DESIGN PROFESSIONAL'S CERTIFICATION STATEMENT AND SIGNATURE THAT THE PERMITTEE'S ES&PC PLAN PROVIDES FOR AN APPROPRIATE AND COMPREHENSIVE SYSTEM OF BMPs AND SAMPLING TO MEET PERMIT REQUIREMENTS AS STATED ON PART IV PAGE 20 OF THE PERMIT.

RESPONSE: PLEASE SEE THE DESIGN PROFESSIONAL'S 7 DAY VISIT CERTIFICATION ON SECTION ON THIS SHEET.
13. REQUIREMENT: DESIGN PROFESSIONAL'S CERTIFICATION STATEMENT AND SIGNATURE THAT THE PERMITTEE'S ES&PC PLAN PROVIDES REPRESENTATIVE SAMPLING AS STATED ON PART IV D.6.c(3) PAGE 37 OF THE PERMIT AS APPLICABLE.

RESPONSE: PLEASE SEE THE DESIGN PROFESSIONAL'S 7 DAY VISIT CERTIFICATION ON SECTION ON THIS SHEET.
14. REQUIREMENT: CLEARLY NOTE THE STATEMENT THAT "THE DESIGN PROFESSIONAL WHO PREPARED THE ES&PC PLAN IS TO INSPECT THE INSTALLATION OF THE INITIAL SEDIMENT STORAGE REQUIREMENTS AND PERIMETER CONTROL BMPs WITHIN 7 DAYS AFTER INSTALLATION." IN ACCORDANCE WITH PART IV A.5 PAGE 26 OF THE PERMIT.

RESPONSE: PLEASE SEE THE DESIGN PROFESSIONAL'S 7 DAY VISIT CERTIFICATION ON SECTION ON THIS SHEET.
15. REQUIREMENT: CLEARLY NOTE THE STATEMENT THAT "NON-EXEMPT ACTIVITIES SHALL NOT BE CONDUCTED WITHIN THE 25 OR 50-FOOT UNDISTURBED STREAM BUFFERS AS MEASURED FROM THE POINT OF WRESTED VEGETATION OR WITHIN 25-FEET OF THE COASTAL MARSHLAND BUFFER AS MEASURED FROM THE JURISDICTIONAL DETERMINATION LINE WITHOUT FIRST ACQUIRING THE NECESSARY VARIANCES AND PERMITS."

RESPONSE: NON-EXEMPT ACTIVITIES SHALL NOT BE CONDUCTED WITHIN THE 25 OR 50-FOOT UNDISTURBED STREAM BUFFERS AS MEASURED FROM THE POINT OF WRESTED VEGETATION OR WITH 25-FEET OF THE COASTAL MARSHLAND BUFFER AS MEASURED FROM THE JURISDICTIONAL DETERMINATION LINE WITHOUT FIRST ACQUIRING THE NECESSARY VARIANCES AND PERMITS.
16. REQUIREMENT: PROVIDE A DESCRIPTION OF ANY BUFFER ENCROACHMENTS AND INDICATE WHETHER A BUFFER VARIANCE IS REQUIRED.

RESPONSE: THIS PROJECT SHOULD NOT ENCRACH ON ANY BUFFERS.
17. REQUIREMENT: CLEARLY NOTE THE STATEMENT THAT "AMENDMENTS/REVISIONS TO THE ES&PC PLAN WHICH HAVE A SIGNIFICANT EFFECT ON BMPs WITH A HYDRAULIC COMPONENT MUST BE CERTIFIED BY THE DESIGN PROFESSIONAL."

RESPONSE: AMENDMENTS/REVISIONS TO THE ES&PC PLAN WHICH HAVE A SIGNIFICANT EFFECT ON BMPs WITH A HYDRAULIC COMPONENT MUST BE CERTIFIED BY THE DESIGN PROFESSIONAL.
18. REQUIREMENT: CLEARLY NOTE THE STATEMENT THE "WASTE MATERIALS SHALL NOT BE DISCHARGED TO WATERS OF THE STATE, EXCEPT AS AUTHORIZED BY A SECTION 404 PERMIT."

RESPONSE: WASTE MATERIALS SHALL NOT BE DISCHARGED TO WATERS OF THE STATE, EXCEPT AS AUTHORIZED BY A SECTION 404 PERMIT.

19. REQUIREMENT: CLEARLY NOTE THE STATEMENT THAT "THE ESCAPE OF SEDIMENT FROM THE SITE SHALL BE PREVENTED BY THE INSTALLATION OF EROSION AND SEDIMENT CONTROL MEASURES AND PRACTICES PRIOR TO LAND DISTURBING ACTIVITIES."

RESPONSE: THE ESCAPE OF SEDIMENT FROM THE SITE SHALL BE PREVENTED BY THE INSTALLATION OF EROSION AND SEDIMENT CONTROL MEASURES AND PRACTICES PRIOR TO LAND DISTURBING ACTIVITIES.
20. REQUIREMENT: CLEARLY NOTE STATEMENT THAT "EROSION CONTROL MEASURES WILL BE MAINTAINED AT ALL TIMES. IF FULL IMPLEMENTATION OF THE APPROVED PLAN DOES NOT PROVIDE FOR EFFECTIVE EROSION CONTROL, ADDITIONAL EROSION AND SEDIMENT CONTROL MEASURES SHALL BE IMPLEMENTED TO CONTROL OR TREAT THE SEDIMENT SOURCE."

RESPONSE: EROSION CONTROL MEASURES WILL BE MAINTAINED AT ALL TIMES. IF FULL IMPLEMENTATION OF THE APPROVED PLAN DOES NOT PROVIDE FOR EFFECTIVE EROSION CONTROL, ADDITIONAL EROSION AND SEDIMENT CONTROL MEASURES SHALL BE IMPLEMENTED TO CONTROL OR TREAT THE SEDIMENT SOURCE.
21. REQUIREMENT: CLEARLY NOTE THE STATEMENT "ANY DISTURBED AREA LEFT EXPOSED FOR A PERIOD GREATER THAN 14 DAYS SHALL BE STABILIZED WITH MULCH OR TEMPORARY SEEDING."

RESPONSE: ANY DISTURBED AREA LEFT EXPOSED FOR A PERIOD GREATER THAN 14 DAYS SHALL BE STABILIZED WITH MULCH OR TEMPORARY SEEDING. SEE MULCHING AND VEGETATIVE PLAN REQUIREMENTS ON DETAIL SHEETS.
22. REQUIREMENT: ANY CONSTRUCTION ACTIVITY WHICH DISCHARGES STORM WATER INTO AN IMPAIRED STREAM SEGMENT, OR WITHIN 1 LINEAR MILE UPSTREAM OF AND WITHIN THE SAME WATERSHED AS, ANY PORTION OF AN BIOTA IMPAIRED STREAM SEGMENT MUST COMPLY WITH PART II, C. OF THE PERMIT. INCLUDE THE COMPLETED APPENDIX 1 LISTING ALL THE BMPs THAT WILL BE USED FOR THOSE AREAS OF THE SITE WHICH DISCHARGE TO THE IMPAIRED STREAM SEGMENT.

RESPONSE: NO CONSTRUCTION ACTIVITY WILL DISCHARGE IN STORM WATER INTO AN IMPAIRED STREAM OR 1 LINEAR MILE UPSTREAM OF AND WITHIN THE SAME WATER SHED AS, ANY PORTION OF AN BIOTA IMPAIRED STREAM SEGMENT. THE SITE IS NOT LOCATED WITHIN ONE MILE OF AN IMPAIRED STREAM.
23. REQUIREMENT: IF A TMDL IMPLEMENTATION PLAN FOR SEDIMENT HAS BEEN FINALIZED FOR THE IMPAIRED STREAM SEGMENT (IDENTIFIED IN ITEM 22 ABOVE) AT LEAST SIX MONTHS PRIOR TO SUBMITTAL OF NOI, THE ES&PC PLAN MUST ADDRESS ANY SITE SPECIFIC CONDITIONS OR REQUIREMENTS INCLUDED IN THE TMDL IMPLEMENTATION PLAN.

RESPONSE: NO TMDL IMPLEMENTATION PLAN IS NEEDED FOR THIS SITE.
24. REQUIREMENT: BMPs FOR CONCRETE WASHDOWN OF TOOLS, CONCRETE MIXER CHUTES, HOPPERS AND THE REAR OF THE VEHICLES. WASHOUT OF THE DRUM AT THE CONSTRUCTION SITE IS PROHIBITED.

RESPONSE: A CONCRETE WASHOUT AREA HAS BEEN ILLUSTRATED ON EACH EROSION CONTROL SHEET. NO CONCRETE TRUCKS WILL BE ALLOWED TO WASH OUT OR DISCHARGE SURPLUS CONCRETE OR DRUM WASH WATER ON-SITE.
25. REQUIREMENT: PROVIDE BMPs FOR THE REMEDIATION OF ALL PETROLEUM SPILLS AND LEAKS.

RESPONSE:
 - CONTAINERS FOR PRODUCTS SUCH AS FUELS, LUBRICANTS AND TARS WILL BE INSPECTED DAILY FOR LEAKS AND SPILLS. THIS INCLUDES ON-SITE VEHICLE AND MACHINERY DAILY INSPECTIONS AND REGULAR PREVENTATIVE MAINTENANCE OF SUCH EQUIPMENT. EQUIPMENT MAINTENANCE AREAS WILL BE LOCATED AWAY FROM STATE WATER, NATURAL DRAINS AND STORM WATER DRAINAGE INLETS. IN ADDITION, TEMPORARY FUELING TANKS SHALL HAVE A SECONDARY CONTAINMENT LINER TO PREVENT/MINIMIZE SITE CONTAMINATION. DISCHARGE OF OILS, FUELS AND LUBRICANTS IS PROHIBITED. PROPER DISPOSAL METHODS WILL INCLUDE COLLECTION IN A SUITABLE CONTAINER AND DISPOSAL AS REQUIRED BY LOCAL AND STATE REGULATIONS.LOCAL, STATE AND MANUFACTURER'S RECOMMENDED METHODS FOR SPILL CLEANUP WILL BE CLEARLY POSTED AND PROCEDURES WILL BE MADE AVAILABLE TO SITE PERSONNEL.
 - MATERIAL AND EQUIPMENT NECESSARY FOR SPILL CLEANUP WILL BE KEPT IN THE MATERIAL STORAGE AREAS. TYPICAL MATERIALS AND EQUIPMENT INCLUDES, BUT IS NOT LIMITED TO, BROOMS, DUSTPANS, MOPS, RAGS, GLOVES, GOGGLES, CAT LITTER, SAND, SAWDUST AND PROPERLY LABELED PLASTIC AND METAL WASTE CONTAINERS.
 - SPILL PREVENTION PRACTICES AND PROCEDURES WILL BE REVIEWED AFTER A SPILL AND ADJUSTED AS NECESSARY TO PREVENT FUTURE SPILLS.
 - ALL SPILLS WILL BE CLEANED UP IMMEDIATELY UPON DISCOVERY. ALL SPILLS WILL BE REPORTED AS REQUIRED BY LOCAL, STATE AND FEDERAL REGULATIONS.
 - FOR SPILLS THAT IMPACT SURFACE WATER (LEAVE A SHEEN ON SURFACE WATER), THE NATIONAL RESPONSE CENTER (NRC) WILL BE CONTACTED WITHIN 24 HOURS AT 1-800-424-8802.
 - FOR SPILLS OF AN UNKNOWN AMOUNT, THE NATIONAL RESPONSE CENTER (NRC) WILL BE CONTACTED WITHIN 24 HOURS AT 1-800-424-8802.
 - FOR SPILLS GREATER THAN 25 GALLONS AND NO SURFACE WATER IMPACTS, THE GEORGIA EPD WILL BE CONTACTED WITHIN 24 HOURS.
 - FOR SPILLS LESS THAN 25 GALLONS AND NO SURFACE WATER IMPACTS, THE SPILL WILL BE CLEANED UP AND LOCAL AGENCIES WILL BE CONTACTED AS REQUIRED.
 - THE CONTRACTOR SHALL NOTIFY THE LICENSED PROFESSIONAL WHO PREPARED THIS PLAN IF MORE THAN 1320 GALLONS OF PETROLUUM IS STORED ON SITE (THIS INCLUDES CAPACITIES OF EQUIPMENT) OR IF ANY ONE PIECE OF EQUIPMENT HAS A CAPACITY GREATER THAN 660 GALLONS. THE CONTRACTOR WILL NEED A SPILL PREVENTION CONTAINMENT AND COUNTERMEASURES PLAN PREPARED BY THAT LICENSED PROFESSIONAL.
26. REQUIREMENT: DESCRIPTION OF THE MEASURES THAT WILL BE INSTALLED DURING THE CONSTRUCTION PROCESS TO CONTROL POLLUTANTS IN STORM WATER THAT WILL OCCUR AFTER CONSTRUCTION OPERATIONS HAVE BEEN COMPLETED.

RESPONSE:
 - DISTURBED AREA STABILIZATION (WITH PERMANENT VEGETATION)
 - USED TO PROVIDE A PROTECTED COVER FOR EXPOSED AREAS INCLUDING CUTS, FILLS, DAMS, AND OTHER DENUDEED AREAS.
 - FOR UNPAVED AREAS AND AREAS NOT COVERED BY PERMANENT STRUCTURES, AT LEAST 70% OF THE SOIL SURFACE IS UNIFORMLY COVERED IN PERMANENT VEGETATION OR EQUIVALENT PERMANENT STABILIZATION MEASURES.
 - PERMANENT VEGETATION SHALL CONSIST OF: PLANTED TREES, SHRUBS, PERENNIAL VINES; A CROP OF PERENNIAL VEGETATION APPROPRIATE FOR THE REGION, SUCH THAT WITHIN THE GROWING SEASON A 70% COVERAGE BY PERENNIAL VEGETATION SHALL BE ACHIEVED
 - USE CONVENTIONAL PLANTING METHODS WHEN POSSIBLE.
 - WHEN MIXED PLANTINGS ARE DONE DURING MARGINAL PLANTING PERIODS, COMPANION CROPS SHALL BE USED.
 - IRRIGATION SHOULD BE USED WHEN THE SOIL IS DRY OR WHEN SUMMER PLANTINGS ARE DONE.
 - LOW MAINTENANCE PLANTS, AS WELL AS NATIVES, SHOULD BE USED TO ENSURE LONG-LASTING EROSION CONTROL.
 - MOWING SHOULD NOT BE PERFORMED DURING QUAIL NESTING SEASON (MAY TO SEPTEMBER).
 - WILDLIFE PLANTINGS SHOULD BE INCLUDED IN CRITICAL AREA PLANTINGS.
 - VERTICAL BANKS SHALL BE SLOPED TO ENABLE PLANT ESTABLISHMENT.
 - AGRICULTURAL LIME IS REQUIRED AT THE RATE OF ONE TO TWO TONS PER ACRE UNLESS SOIL TESTS INDICATE OTHERWISE. GRADED AREAS REQUIRE LIME APPLICATION. IF LIME IS ALLIED WITHIN SIX MONTHS OF PLANTING PERMANENT PERENNIAL VEGETATION, ADDITIONAL LIME IS NOT REQUIRED.
 - AGRICULTURAL LIME SHALL BE WITHIN THE SPECIFICATIONS OF THE GEORGIA DEPARTMENT OF AGRICULTURE. LIME SPREAD BY CONVENTIONAL EQUIPMENT SHALL BE "GROUND LIMESTONE" AND LIME SPREAD BY HYDRAULIC SEEDING EQUIPMENT SHALL BE "FINELY GROUND LIMESTONE"
 - WHEN HYDRAULIC SEEDING EQUIPMENT IS USED, THE INITIAL FERTILIZER SHALL BE MIXED WITH SEED, INOCULANT (IF NEEDED), AND WOOD CELLULOSE OR WOOD PULP FIBER MULCH AND APPLIED IN A SLURRY. THE INOCULANT, IF NEEDED, SHALL BE MIXED WITH THE SEED PRIOR TO BEING PLACED INTO THE HYDRAULIC SEEDER. THE SLURRY MIXTURE WILL BE AGITATED DURING APPLICATION TO KEEP THE INGREDIENTS THOROUGHLY MIXED. THE MIXTURE WILL BE SPREAD UNIFORMLY OVER THE AREA WITHIN ONE HOUR AFTER BEING PLACED IN THE HYDROSEEDER.
 - WHEN CONVENTIONAL PLANTING IS TO BE DONE, LIME AND FERTILIZER SHALL BE APPLIED UNIFORMLY IN ONE OF THE FOLLOWING WAYS: 1. APPLY BEFORE LAND PREPARATION SO THAT IT WILL BE MIXED WITH THE SOIL DURING SEEDBED PREPARATION. 2. MIX WITH THE SOIL USED TO FILL THE HOLES, DISTRIBUTE IN FURROWS. 3. BROADCAST AFTER STEEP SURFACES ARE SCARPED, PITTED OR RENEWED. 4. FERTILIZER PELLET SHALL BE PLACED AT ROOT DEPTH IN THE CLOSING HOLE BESIDE EACH PINE TREE SEEDLING.
 - MULCH IS REQUIRED FOR ALL PERMANENT VEGETATION APPLICATIONS. MULCH APPLIED TO SEEDED AREAS SHALL ACHIEVE 75% SOIL COVER. STRAW OR HAY MULCH WILL BE SPREAD UNIFORMLY WITHIN 24 HOURS AFTER SEEDING AND/OR PLANTING. THE MULCH MAY BE SPREAD BY BLOWER-TYPE SPREADING EQUIPMENT, OTHER SPREADING EQUIPMENT OR BY HAND. MULCH SHALL BE APPLIED TO COVER 75% OF THE SOIL SURFACE. WOOD CELLULOSE OR WOOD FIBER MULCH SHALL BE APPLIED UNIFORMLY WITH HYDRAULIC SEEDING EQUIPMENT.
 - MOW SERICEA LESPEDEZA ONLY AFTER FROST TO ENSURE THAT THE SEEDS ARE MATURE. MOW BETWEEN NOVEMBER AND MARCH. BERMUDAGRASS, BAHIA GRASS AND TALL FESCUE MAY BE MOWED AS DESIRED. MAINTAIN AT LEAST 6 INCHES OF TOP GROWTH UNDER ANY USE AND MANAGEMENT. MODERATE USE OF TOP GROWTH IS BENEFICIAL AFTER ESTABLISHMENT. EXCLUDE TRAFFIC UNTIL THE PLANTS ARE WELL ESTABLISHED. BECAUSE OF THE QUAIL NESTING SEASON, MOWING SHOULD NOT TAKE PLACE BETWEEN MAY AND SEPTEMBER.
 - APPLY ONE TON OF AGRICULTURAL LIME EVERY 4 TO 6 YEARS OR AS INDICATED BY SOIL TESTS. SOIL TESTS CAN BE CONDUCTED TO DETERMINE MORE ACCURATE REQUIREMENTS IF DESIRED.
 - VEGETATED WATERWAY OR STORMWATER CONVEYANCE
 - A NATURAL OR CONSTRUCTED CHANNEL THAT IS SHAPED OR GRADED TO REQUIRED DIMENSIONS AND ESTABLISHED IN SUITABLE VEGETATION FOR THE STABLE CONVEYANCE OF RUNOFF WITHOUT CAUSING DAMAGE EITHER BY EROSION OR BY FLOODING.
 - THIS STANDARD APPLIES TO ALL SITES WHERE ADDED CHANNEL CAPACITY AND/OR STABILIZATION IS REQUIRED TO CONTROL EROSION RESULTING FROM CONCENTRATED RUNOFF AND WHERE SUCH CONTROL CAN BE ACHIEVED BY THIS PRACTICE ALONE OR IN COMBINATION WITH OTHERS
 - THE MINIMUM CAPACITY SHALL BE THAT REQUIRED TO CONVEY THE PEAK RUNOFF EXPECTED FROM A 25-YEAR, 24-HOUR STORM OR THE STORM SPECIFIED IN THE GSWCC EROSION AND SEDIMENT CONTROL MANUAL.
 - CONSTRUCTION SPECIFICATIONS
 - ALL TREES, BRUSH, STUMPS, OBSTRUCTIONS, AND OTHER OBJECTIONABLE MATERIAL SHALL BE REMOVED AND DISPOSED OF SO AS NOT TO INTERFERE WITH THE PROPER FUNCTIONING OF THE WATERWAY.
 - THE WATERWAY OR OUTLET SHALL BE EXCAVATED OR SHAPED TO LINE, GRADE, AND CROSS SECTION AS REQUIRED TO MEET THE CRITERIA SPECIFIED HEREIN. IT WILL BE FREE OF BANK PROJECTIONS OR OTHER IRREGULARITIES WHICH WILL IMPED E NORMAL FLOW. IF THE CHANNEL MUST HAVE EROSION PROTECTION OTHER THAN VEGETATION, THE LINING SHALL NOT COMPROMISE THE CAPACITY OF THE EMERGENCY SPILLWAY, I.E. THE CHANNEL SHALL BE OVER-EXCAVATED SO THAT THE LINING WILL BE FLUSH WITH THE SLOPE SURFACE.
 - FILLS SHALL BE COMPACTED AS NEEDED TO PREVENT UNEQUAL SETTLEMENT THAT WOULD CAUSE DAMAGE IN THE COMPLETED WATERWAY.
 - ALL EARTH REMOVED AND NOT NEEDED IN CONSTRUCTION SHALL BE SPREAD OR DISPOSED OF SO THAT IT WILL NOT INTERFERE WITH WATERWAY FUNCTIONING.
 - STABILIZATION: APPLICABLE VEGETATIVE STANDARDS SHALL BE FOLLOWED FOR TIME OF SEEDING, SPRIGGING OR SODDING, LINING AND FERTILIZING, AND SITE AND SEEDBED PREPARATION. EROSION CONTROL BLANKETS OR MATTING OR SOD SHALL BE USED TO AID IN THE ESTABLISHMENT OF VEGETATION. INSTALLATION METHODS SHOULD FOLLOW MANUFACTURER RECOMMENDATIONS.
 - MULCHING SHALL BE A REQUIREMENT FOR ALL SEEDED OR SPRIGGED CHANNELS. TEMPORARY PROTECTION DURING ESTABLISHMENT SHOULD BE PROVIDED WHEN CONDITIONS PERMIT THROUGH TEMPORARY DIVERSIONS OR OTHER MEANS TO DISPOSE OF WATER.

27. DESCRIPTION OF PRACTICES TO PROVIDE COVER FOR BUILDING MATERIALS AND BUILDING PRODUCTIONS ON SITE.

RESPONSE: PLASTIC SHEETING OR TEMPORARY ROOFS TO BE UTILIZED TO COVER BUILDING MATERIALS, BUILDING PRODUCTS, CONSTRUCTION WASTE, TRASH, LANDSCAPE MATERIALS, FERTILIZERS, PESTICIDES, HERBICIDES, DETERGENTS, SANITARY WASTE AND OTHER MATERIALS IN ORDER TO MINIMIZE EXPOSURE TO PRECIPITATION AND TO STORMWATER.
28. REQUIREMENT: DESCRIPTION OF THE PRACTICES THAT WILL BE USED TO REDUCE THE POLLUTANTS IN STORM WATER DISCHARGES.

RESPONSE:
 - PRODUCT SPECIFIC PRACTICES
 - PETROLEUM BASED PRODUCTS - CONTAINERS FOR PRODUCTS SUCH AS FUELS, LUBRICANTS, AND TARS WILL BE INSPECTED DAILY FOR LEAKS AND SPILLS. THIS INCLUDES ON-SITE VEHICLE AND MACHINERY DAILY INSPECTIONS AND REGULAR PREVENTATIVE MAINTENANCE OF SUCH EQUIPMENT. EQUIPMENT MAINTENANCE AREAS WILL BE LOCATED AWAY FROM STATE WATER, NATURAL DRAINS, AND STORM WATER DRAINAGE INLETS. IN ADDITION, TEMPORARY FUELING TANKS SHALL HAVE A SECONDARY CONTAINMENT LINER TO PREVENT/MINIMIZE SITE CONTAMINATION. DISCHARGE OF OILS, FUELS, AND LUBRICANTS IS PROHIBITED. PROPER DISPOSAL METHODS WILL INCLUDE COLLECTION IN A SUITABLE CONTAINER AND DISPOSAL AS REQUIRED BY LOCAL AND STATE REGULATIONS.
 - POINTS/FINISHES/SOLVENTS - ALL PRODUCTS WILL BE STORED IN TIGHTLY SEALED ORIGINAL CONTAINERS WHEN NOT IN USE. EXCESS PRODUCT WILL NOT BE DISCHARGED TO THE STORM WATER COLLECTION SYSTEM. EXCESS PRODUCT MATERIALS USED WITH THESE PRODUCTS AND PRODUCT CONTAINERS WILL BE DISPOSED OF ACCORDING TO MANUFACTURER'S SPECIFICATIONS AND RECOMMENDATIONS.
 - CONCRETE TRUCK WASHING - A CONCRETE WASHOUT AREA HAS BEEN DETAILED FOR THIS SITE.
 - FERTILIZER/HERBICIDES - THESE PRODUCTS WILL BE APPLIED AT RATES THAT DO NOT EXCEED THE MANUFACTURER'S SPECIFICATIONS OR ABOVE THE GUIDELINES SET FORTH IN THE CROP ESTABLISHMENT OR IN THE GSWCC MANUAL FOR THE EROSION AND SEDIMENT CONTROL IN GEORGIA. ANY STORAGE OF THESE MATERIALS WILL BE UNDER ROOF IN SEALED CONTAINERS.
 - BUILDING MATERIALS - NO BUILDING OR CONSTRUCTION MATERIALS WILL BE BURIED OR DISPOSED OF ONSITE. ALL SUCH MATERIAL WILL BE DISPOSED OF IN PROPER WASTE DISPOSAL PROCEDURES
 - PRIOR TO THE LAND DISTURBING CONSTRUCTION, THE CONTRACTOR SHALL SCHEDULE A PRE-CONSTRUCTION MEETING WITH THE AREA SITE DEVELOPMENT INSPECTOR.
 - OTHER PRACTICES
 - THE CONTRACTOR SHALL OBSERVE THE PROJECT SEQUENCE SHOWN ON THE PLANS. THE CONTRACTOR SHALL MAINTAIN CAREFUL SCHEDULING AND PERFORMANCE TO INSURE THAT LAND STRIPED OF ITS NATURAL COVER IS EXPOSED ONLY IN SMALL QUANTITIES.
 - A COPY OF THE APPROVED LAND DISTURBANCE PLAN AND PERMIT SHALL BE PRESENT ON THE SITE AT ALL TIMES.
- PRIOR TO COMMENCING LAND DISTURBANCE ACTIVITY, THE LIMITS OF LAND DISTURBANCE AND ALL STREAM BUFFERS SHALL BE CLEARLY AND ACCURATELY DEMARCATED WITH STAKES, RIBBONS, OR OTHER APPROPRIATE MEANS. THE LOCATION AND EXTENT OF ALL AUTHORIZED LAND DISTURBANCE ACTIVITY SHALL BE DEMARCATED FOR THE DURATION OF THE CONSTRUCTION ACTIVITY. NO LAND DISTURBANCE SHALL OCCUR OUTSIDE THE APPROVED LIMITS INDICATED ON THE APPROVED PLANS.
 - THE FOLLOWING INITIAL EROSION CONTROL MEASURES SHALL BE IMPLEMENTED PRIOR TO ANY OTHER CONSTRUCTION ACTIVITY.
 - THE CONSTRUCTION EXIT, CONSISTING OF A MINIMUM PAD SIZE OF 20 FEET BY 50 FEET WITH A MINIMUM OF 6" THICK STONE, SHALL BE PLACED AS SHOWN ON THE PLAN. THE STONE SIZE SHOULD CONSIST OF COURSE AGGREGATE BETWEEN 1-1/2" & 3-1/2" IN DIAMETER AND OVERLAD ON A GEOTEXTILE UNDERLINER. THE GEOTEXTILE UNDERLINER SHALL MEET THE REQUIREMENTS OF AASHTO M280-86, SECTION 7.3 SEPARATION REQUIREMENTS.
 - IMMEDIATELY AFTER THE ESTABLISHMENT OF CONSTRUCTION ENTRANCE/EXITS, ALL PERIMETER EROSION CONTROL AND STORM WATER MANAGEMENT DEVICES SHALL BE INSTALLED AS SHOWN ON THE INITIAL PHASE EROSION CONTROL PLAN.
 - SILT FENCE SHOULD BE INSTALLED AT THE PERIMETER OF THE DISTURBED AREA AS SHOWN ON THE PLAN. THE SILT FENCE SHOULD BE PLACED IN ACCORDANCE WITH THE MANUAL FOR EROSION CONTROL IN GEORGIA. THE SILT FENCE SHOULD BE KEPT ERECT AT ALL TIMES AND REPAIRED WHEN REQUESTED BY THE SITE INSPECTOR OR THE PROJECT DESIGN PROFESSIONAL OF RECORD. SILT SHOULD BE REMOVED WHEN ACCUMULATION REACHES 1/2 HEIGHT OF THE BARRIER. THE PERIMETER SILT FENCE SHOULD BE INSPECTED DAILY FOR ANY FAILURES. ANY FAILURES OF SAID FENCING SHOULD BE REPAIRED IMMEDIATELY.
 - AFTER INSTALLATION OF INITIAL EROSION CONTROL MEASURES THE SITE CONTRACTOR SHALL SCHEDULE AN INSPECTION BY THE PROJECT DESIGN PROFESSIONAL. NO OTHER CONSTRUCTION ACTIVITIES SHALL OCCUR UNTIL THE PROJECT DESIGN PROFESSIONAL APPROVES THE INSTALLATION OF SAID EROSION CONTROL MEASURES. IF UNFORESEEN CONDITIONS EXIST IN THE FIELD THAT WARRANT ADDITIONAL EROSION CONTROL MEASURES, THE CONTRACTOR MUST CONSTRUCT ANY ADDITIONAL EROSION CONTROL DEVICES DEEMED NECESSARY BY THE SITE INSPECTION.
 - AFTER APPROVAL OF THE INITIAL EROSION CONTROL INSTALLATION, THE CONTRACTOR MAY PROCEED WITH CLEARING AND GRUBBING ACTIVITIES. AS CLEARING PERMITS, THE CONTRACTOR SHALL CONSTRUCT TEMPORARY SEDIMENT PONDS AND DIVERSION DIKES AS SHOWN ON THE INITIAL PHASE PLAN TO CONTROL EROSION AND STORM WATER RUN OFF.
 - NO BURN OR BURY PITS SHALL BE PERMITTED ON THE CONSTRUCTION SITE WITHOUT WRITTEN PERMISSION BY THE OWNER AND/OR THE ENGINEER OF RECORD.
- ADDITIONAL SILT BARRIERS MUST BE PLACED AS SHOWN ON THE PLAN AS ACCESS IS OBTAINED DURING CLEARING. NO GRADING SHALL TAKE PLACE UNTIL SILT BARRIER INSTALLATION AND SEDIMENT PONDS ARE CONSTRUCTED AS SHOWN ON THE INITIAL PHASE EROSION CONTROL PLAN.
 - MULCH OR TEMPORARY GRASSING SHALL BE APPLIED TO ALL EXPOSED AREAS WITHIN 7 DAYS OF LAND DISTURBANCE.
- ALL DISTURBED AREAS LEFT MULCHED AFTER 30 DAYS SHALL BE STABILIZED WITH TEMPORARY VEGETATION.
 - SEDIMENT AND EROSION CONTROL MEASURES SHOULD BE CHECKED AFTER EACH RAIN EVENT. EACH DEVICE IS TO BE MAINTAINED OR REPLACED IF SEDIMENT ACCUMULATION HAS REACHED ONE HALF THE CAPACITY OF THE DEVICE. ADDITIONAL DEVICES MUST BE INSTALLED IF NEW CHANNELS HAVE DEVELOPED.
- THE CONSTRUCTION EXIT SHALL BE MAINTAINED IN A CONDITION WHICH WILL PREVENT TRACK OR FLOW OF MUD ONTO PUBLIC RIGHT-OF-WAY. THIS MAY REQUIRE PERIODIC TOP DRESSING WITH 1-3" OF STONE, AS CONDITIONS DEMAND. ALL MATERIALS SPILLED, DROPPED, WASHED, OR TRACKED FROM VEHICLE ONTO PUBLIC ROADWAY OR INTO STORM DRAIN MUST BE REMOVED IMMEDIATELY.
- CONTRACTOR SHALL INSPECT CONTROL MEASURES AT THE END OF EACH WORKING DAY TO ENSURE MEASURES ARE FUNCTIONING PROPERLY.
- EROSION CONTROL MEASURES WILL BE MAINTAINED AT ALL TIMES. IF FULL IMPLEMENTATION OF THE APPROVED PLAN DOES NOT PROVIDE FOR EFFECTIVE EROSION CONTROL, ADDITIONAL EROSION AND SEDIMENT CONTROL MEASURES SHALL BE IMPLEMENTED TO CONTROL OR TREAT THE SEDIMENT SOURCE AS DIRECTED BY THE ON-SITE INSPECTOR OR THE CIVIL ENGINEER.FAILURE TO INSTALL, OPERATE, OR MAINTAIN ALL EROSION CONTROL MEASURES WILL RESULT IN ALL CONSTRUCTION BEING STOPPED ON THE JOB UNTIL SUCH MEASURES ARE CORRECTED BACK TO THE APPROVED EROSION CONTROL PLANS.
- THE FOLLOWING EROSION CONTROL MEASURES SHALL BE IMPLEMENTED DURING THE PRELIMINARY GRADING PHASE OF CONSTRUCTION:
- INLET SEDIMENT TRAPS WILL BE INSTALLED AROUND ALL NEW INLETS.
- EROSION CONTROL DEVICES SHALL BE INSTALLED IMMEDIATELY AFTER GROUND DISTURBANCE OCCURS. THE LOCATION OF SOME OF THE EROSION CONTROL DEVICES MAY HAVE TO BE ALTERED FROM THAT SHOWN ON THE APPROVED PLANS IF DRAINAGE PATTERNS DURING CONSTRUCTION ARE DIFFERENT FROM THE PROPOSED DRAINAGE PATTERNS. IT IS THE CONTRACTOR'S RESPONSIBILITY TO ACCOMPLISH EROSION CONTROL FOR ALL DRAINAGE PATTERNS CREATED AT VARIOUS STAGES DURING CONSTRUCTION. ANY DIFFICULTY IN CONTROLLING EROSION DURING ANY PHASE OF CONSTRUCTION SHALL BE REPORTED TO THE DESIGN PROFESSIONAL IMMEDIATELY.
- STORM DRAIN OUTLET PROTECTION SHALL BE PLACED AT ALL OUTLET HEADWALLS AS SOON AS THE HEADWALL IS CONSTRUCTED. SEE SEPARATE DETAILS FOR ADDITIONAL INFORMATION.
- ALL DRAINAGE SWALES SHALL BE APPLIED WITH VEGETATIVE COVER AS SOON AS FINAL GRADE IS ACHIEVED.
- MULCH OR TEMPORARY GRASSING SHALL BE APPLIED TO ALL EXPOSED AREAS WITHIN 7 DAYS OF LAND DISTURBANCE.
- SEDIMENT AND EROSION CONTROL MEASURES SHOULD BE CHECKED AFTER EACH RAIN EVENT. EACH DEVICE IS TO BE MAINTAINED OR REPLACED IF SEDIMENT ACCUMULATION HAS REACHED ONE HALF THE CAPACITY OF THE DEVICE. ADDITIONAL DEVICES MUST BE INSTALLED IF NEW CHANNELS HAVE DEVELOPED.
- INSTALL TEMPORARY SEDIMENT TRAP.
29. REQUIREMENT: DESCRIPTION AND CHART OR TIMELINE OF THE INTENDED SEQUENCE OF MAJOR ACTIVITIES WHICH DISTURB SOILS FOR THE MAJOR PORTION OF THE SITE (I.E., INITIAL PERIMETER AND SEDIMENT STORAGE BMPs, CLEARING AND GRUBBING ACTIVITIES, EXCAVATION ACTIVITIES, UTILITY ACTIVITIES, TEMPORARY AND FINAL STABILIZATION).

RESPONSE:
- | INFRASTRUCTURE | 2022 | | | | | |
|--|------|-----|-----|-----|-----|-----|
| | JUL | AUG | SEP | OCT | NOV | DEC |
| INSTALLATION OF CONSTRUCTION EXIT, PERMETER SILT FENCE, TEMPORARY SEDIMENT BASIN & TREE PROTECTION | ■ | | | | | |
| CLEARING & GRUBBING | | ■ | | | | |
| PRELIMINARY GRADING | | ■ | | | | |
| PUMP STATION REHAB | | | ■ | | | |
| INSTALL GRADING PHASE EROSION MEASURES | | | ■ | | | |
| INSTALLATION OF UTILITY LINES (S.S./WATER/STORM) | | | ■ | ■ | | |
| FINE GRADING | | | | ■ | | |
| FINAL LANDSCAPING | | | | | ■ | |
| REMOVE TEMPORARY EROSION MEASURES AND TREE PROTECTION FENCING | | | | | ■ | |
| MAINTENANCE OF EROSION BMPs | ■ | ■ | ■ | ■ | ■ | ■ |
- DESIGN PROFESSIONAL'S CERTIFICATION:
- "I CERTIFY UNDER PENALTY OF LAW THAT THIS PLAN WAS PREPARED AFTER A SITE VISIT TO THE LOCATIONS DESCRIBED HEREIN BY MYSELF OR MY AUTHORIZED AGENT, UNDER MY SUPERVISION."
- "I CERTIFY THAT THE PERMITTEE'S EROSION, SEDIMENTATION AND POLLUTION CONTROL PLAN PROVIDES FOR AN APPROPRIATE AND COMPREHENSIVE SYSTEM OF BEST MANAGEMENT PRACTICES REQUIRED BY THE GEORGIA WATER QUALITY CONTROL ACT AND THE DOCUMENT "MANUAL FOR EROSION AND SEDIMENT CONTROL IN GEORGIA" (MANUAL), PUBLISHED BY THE GEORGIA SOIL AND WATER CONSERVATION COMMISSION AS OF JANUARY 1 OF THE YEAR IN WHICH THE LAND-DISTURBING ACTIVITY WAS PERMITTED, PROVIDES FOR THE SAMPLING OF THE RECEIVING WATER(S) OR THE SAMPLING OF THE STORMWATER OUTFALLS AND THAT THE DESIGNED SYSTEM OF BEST MANAGEMENT PRACTICES AND SAMPLING METHODS IS EXPECTED TO MEET THE REQUIREMENTS CONTAINED IN THE GENERAL NPDES PERMIT NO. GAR100002."
- I AM AWARE THAT THERE ARE SIGNIFICANT PENALTIES FOR SUBMITTING FALSE INFORMATION, INCLUDING THE POSSIBILITY OF FINE AND IMPRISONMENT FOR KNOWING VIOLATIONS."
- GSWCC LEVEL II DESIGN PROFESSIONAL 0000XXXXX
CERTIFICATION #
- DESIGN PROFESSIONAL 7-DAY VISIT CERTIFICATION
- THE DESIGN PROFESSIONAL WHO PREPARED THE EX&PC PLAN IS TO INSPECT THE INSTALLATION OF THE INITIAL SEDIMENT STORAGE REQUIREMENTS AND PERIMETER CONTROL BMPs WITHIN 7 DAYS AFTER INSTALLATION
- DATE OF INSPECTION
I CERTIFY THE SITE WAS IN COMPLIANCE WITH ES&PC PLAN ON THE DATE OF INSPECTION.
- GSWCC LEVEL II DESIGN PROFESSIONAL CERTIFICATION #
- INSPECTION REVEALED THE FOLLOWING DISCREPANCIES FROM THE ES&PC PLAN:
-
- THESE DEFICIENCIES MUST BE ADDRESSED IMMEDIATELY AND A RE-INSPECTION SCHEDULED. WORK SHALL NOT PROCEED ON THE SITE UNTIL DESIGN PROFESSIONAL CERTIFICATION IS OBTAINED.
- PROFESSIONAL SEAL

THIS DRAWING IS THE PROPERTY OF T. R. LONG ENGINEERING, P.C. AND MAY NOT BE REPRODUCED, COPIED, OR PART BE LOANED, IN ANY MANNER WITHOUT THE WRITTEN PERMISSION OF T. R. LONG ENGINEERING, P.C.

THE CONTRACTOR SHALL VERIFY ALL DIMENSIONS CONTAINED WITHIN THIS SET OF DOCUMENTS AND SHALL REPORT ANY DISCREPANCIES TO T. R. LONG ENGINEERING, P.C. FOR IMMEDIATE RESOLUTION.

HINESVILLE:

114 North Commerce Street
Hinesville, Georgia 31313
(912) 368-5664

SAVANNAH:

308 Commercial Drive
Savannah, Georgia 31406
(912) 335-1046

www.trlongeng.com

GEORGIA#11.COM DIAL #11

GSWCC# 0000002134

PINE FOREST
SEWER SYSTEM IMPROVEMENTS
CITY OF PORT WENTWORTH

SHEET NAME:

EROSION CONTROL
NOTES

REVISIONS:

1.

2.

3.

4.

5.

6.

7.

8.

9.

10

INITIAL DATE: 6/22/2022
DRAWN BY: RRC
CHECKED BY: TRL
PROJECT #: 2021-285

SHEET NUMBER:
C7.4

CONCRETE WASHOUT AREA

PURPOSE – PREVENT OR REDUCE THE DISCHARGE OF POLLUTANTS TO STORM WATER FROM CONCRETE WASTE BY CONDUCTING WASHOUT OFFSITE, OR PERFORMING ONSITE WASHOUT IN A DESIGNATED AREA TO PREVENT POLLUTANTS FROM ENTERING SURFACE WATERS OR GROUNDWATER.

CONDITIONS OF USE – CONCRETE WASHOUT AREA BEST MANAGEMENT PRACTICES ARE IMPLEMENTED ON CONSTRUCTION PROJECTS WHERE:

- CONCRETE IS USED AS A CONSTRUCTION MATERIAL.
- IT IS NOT POSSIBLE TO DISPOSE OF ALL CONCRETE WASTEWATER AND WASHOUT OFFSITE (READY MIX PLANT, ETC.).
- CONCRETE TRUCKS, PUMPER, OR OTHER CONCRETE COATED EQUIPMENT ARE WASHED ONSITE.

DESIGN AND INSTALLATION SPECIFICATIONS

- IMPLEMENTATION – THE FOLLOWING STEPS WILL HELP REDUCE STORMWATER POLLUTION FROM CONCRETE WASTES:
- PERFORM WASHOUT OF CONCRETE TRUCKS OFFSITE OR IN DESIGNATED CONCRETE WASHOUT AREAS ONLY.
 - DO NOT WASH OUT CONCRETE TRUCKS ONTO THE GROUND, OR INTO STORM DRAINS, OPEN DITCHES, STREETS, OR STREAMS.
 - DO NOT ALLOW EXCESS CONCRETE TO BE DUMPED ONSITE, EXCEPT IN DESIGNATED CONCRETE WASHOUT AREAS.
 - CONCRETE WASHOUT AREAS MAY BE PREFABRICATED CONCRETE WASHOUT CONTAINERS, OR SELF-INSTALLED STRUCTURES (ABOVE-GRADE OR BELOW-GRADE).
 - PREFABRICATED CONTAINERS ARE MOST RESISTANT TO DAMAGE AND PROTECT AGAINST SPILLS AND LEAKS. COMPANIES MAY OFFER DELIVERY SERVICE AND PROVIDE REGULAR MAINTENANCE AND DISPOSAL OF SOLID AND LIQUID WASTE.
 - IF SELF-INSTALLED CONCRETE WASHOUT AREAS ARE USED, BELOW-GRADE STRUCTURES ARE PREFERRED OVER ABOVE-GRADE STRUCTURES BECAUSE THEY ARE LESS PRONE TO SPILLS AND LEAKS.
 - SELF-INSTALLED ABOVE-GRADE STRUCTURES SHOULD ONLY BE USED IF EXCAVATION IS NOT PRACTICAL.

EDUCATION – THE FOLLOWING EDUCATION PRACTICES ARE RECOMMENDED:

- DISCUSS THE CONCRETE MANAGEMENT TECHNIQUES DESCRIBED IN THIS BEST MANAGEMENT PRACTICE WITH THE READY-MIX CONCRETE SUPPLIER BEFORE ANY DELIVERIES ARE MADE.
- EDUCATE EMPLOYEES AND SUBCONTRACTORS ON THE CONCRETE WASTE MANAGEMENT TECHNIQUES DESCRIBED IN THIS SECTION.
- ARRANGE FOR CONTRACTOR'S SUPERINTENDENT OR LEVEL 1A CERTIFIED PERSONNEL TO OVERSEE AND ENFORCE CONCRETE WASTE MANAGEMENT PROCEDURES.
- A SIGN SHOULD BE INSTALLED ADJACENT TO EACH TEMPORARY CONCRETE WASHOUT FACILITY TO INFORM CONCRETE EQUIPMENT OPERATORS TO UTILIZE THE PROPER FACILITIES.

CONTRACTS – INCORPORATE REQUIREMENTS FOR CONCRETE WASTE MANAGEMENT INTO CONCRETE SUPPLIER AND SUBCONTRACTOR AGREEMENTS.

LOCATION AND PLACEMENT – THE FOLLOWING GUIDELINES SHALL BE USED WHEN LOCATING AND PLACING THE CONCRETE WASH-OUT AREA:

- LOCATE WASHOUT AREA AT LEAST 50 FEET FROM SENSITIVE AREAS SUCH AS STORM DRAINS, OPEN DITCHES, OR WATER BODIES, INCLUDING WETLANDS.
- ALLOW CONVENIENT ACCESS FOR CONCRETE TRUCKS, PREFERABLY NEAR THE AREA WHERE THE CONCRETE IS BEING POURED.
- IF TRUCKS NEED TO LEAVE A PAVED AREA TO ACCESS WASHOUT, PREVENT TRACK-OUT WITH A CONSTRUCTION EXIT.
- THE NUMBER OF FACILITIES YOU INSTALL SHOULD DEPEND ON THE EXPECTED DEMAND FOR STORAGE CAPACITY.
- ON LARGE SITES WITH EXTENSIVE CONCRETE WORK, WASHOUTS SHOULD BE PLACED IN MULTIPLE LOCATIONS FOR EASE OF USE BY CONCRETE TRUCK DRIVERS.

ONSITE TEMPORARY CONCRETE WASHOUT FACILITY, TRANSIT TRUCK WASHOUT PROCEDURES:

- TEMPORARY CONCRETE WASHOUT FACILITIES SHALL BE LOCATED A MINIMUM OF 50 FT. FROM SENSITIVE AREAS INCLUDING STORM DRAIN INLETS, OPEN DRAINAGE FACILITIES, AND WATERCOURSES.
- CONCRETE WASHOUT FACILITIES SHALL BE CONSTRUCTED AND MAINTAINED IN SUFFICIENT QUANTITY AND SIZE TO CONTAIN ALL LIQUID AND CONCRETE WASTE GENERATED BY WASHOUT OPERATIONS.
- APPROXIMATELY 7 GALLONS OF WASH WATER ARE USED TO WASH ONE TRUCK CHUTE.
- APPROXIMATELY 50 GALLONS ARE USED TO WASH OUT THE HOPPER OF A CONCRETE PUMP TRUCK
- WASHOUT OF CONCRETE TRUCKS SHALL BE PERFORMED IN DESIGNATED AREAS ONLY.
- CONCRETE WASHOUT FROM CONCRETE PUMPER BINS CAN BE WASHED INTO CONCRETE PUMPER TRUCKS AND DISCHARGED INTO DESIGNATED WASHOUT AREA OR PROPERLY DISPOSED OF OFFSITE.
- ONCE CONCRETE WASTES ARE WASHED INTO THE DESIGNATED AREA AND ALLOWED TO HARDEN, THE CONCRETE SHOULD BE BROKEN UP, REMOVED, AND DISPOSED OF PER APPLICABLE SOLID WASTE REGULATIONS. DISPOSE OF HARDENED CONCRETE ON A REGULAR BASIS.

TEMPORARY ABOVE-GRADE CONCRETE WASHOUT FACILITY

- TEMPORARY CONCRETE WASHOUT FACILITY (TYPE ABOVE GRADE) SHOULD BE CONSTRUCTED AS SHOWN ON THE DETAILS WITH A RECOMMENDED MINIMUM LENGTH AND MINIMUM WIDTH OF 10 FT., BUT WITH SUFFICIENT QUANTITY AND VOLUME TO CONTAIN ALL LIQUID AND CONCRETE WASTE GENERATED BY WASHOUT OPERATIONS.
- PLASTIC LINING MATERIAL SHOULD BE A MINIMUM OF 10 MIL POLYETHYLENE SHEETING AND SHOULD BE FREE OF HOLES, TEARS, OR OTHER DEFECTS THAT COMPROMISE THE IMPERMEABILITY OF THE MATERIAL.

TEMPORARY BELOW-GRADE CONCRETE WASHOUT FACILITY


- TEMPORARY CONCRETE WASHOUT FACILITIES (TYPE BELOW GRADE) SHOULD BE CONSTRUCTED WITH A RECOMMENDED MINIMUM LENGTH AND MINIMUM WIDTH OF 10 FT. THE QUANTITY AND VOLUME SHOULD BE SUFFICIENT TO CONTAIN ALL LIQUID AND CONCRETE WASTE GENERATED BY WASHOUT OPERATIONS.
- PLASTIC LINING MATERIAL SHALL BE A MINIMUM OF 10 MIL POLYETHYLENE SHEETING AND SHOULD BE FREE OF HOLES, TEARS, OR OTHER DEFECTS THAT COMPROMISE THE IMPERMEABILITY OF THE MATERIAL.
- LINER SEAMS SHALL BE INSTALLED IN ACCORDANCE WITH MANUFACTURERS' RECOMMENDATIONS.
- SOIL BASE SHALL BE PREPARED FREE OF ROCKS OR OTHER DEBRIS THAT MAY CAUSE TEARS OR HOLES IN THE PLASTIC LINING MATERIAL.

INSPECTION AND MAINTENANCE


- INSPECT AND VERIFY THAT CONCRETE WASHOUT BMPs ARE IN PLACE PRIOR TO THE COMMENCEMENT OF CONCRETE WORK.
- DURING PERIODS OF CONCRETE WORK, INSPECT DAILY TO VERIFY CONTINUED PERFORMANCE.
- CHECK OVERALL CONDITION AND PERFORMANCE.
- CHECK REMAINING CAPACITY (% FULL).
- IF USING SELF-INSTALLED WASHOUT FACILITIES, VERIFY PLASTIC LINERS ARE INTACT AND SIDEWALLS ARE NOT DAMAGED.
- IF USING PREFABRICATED CONTAINERS, CHECK FOR LEAKS.
- WASHOUT FACILITIES SHALL BE MAINTAINED TO PROVIDE ADEQUATE HOLDING CAPACITY WITH A MINIMUM FREEBOARD OF 12 INCHES.
- WASHOUT FACILITIES MUST BE CLEANED, OR NEW FACILITIES MUST BE CONSTRUCTED AND READY FOR USE ONCE THE WASHOUT IS 75% FULL.
- IF THE WASHOUT IS NEARING CAPACITY, VACUUM AND DISPOSE OF THE WASTE MATERIAL IN AN APPROVED MANNER.
- DO NOT DISCHARGE LIQUID OR SLURRY TO WATERWAYS, STORM DRAINS OR DIRECTLY ONTO GROUND.
- DO NOT USE SANITARY SEWER WITHOUT LOCAL APPROVAL.
- PLACE A SECURE, NON-COLLAPSING, NON-WATER COLLECTING COVER OVER THE CONCRETE WASHOUT FACILITY PRIOR TO PRECIPITATION TO PREVENT ACCUMULATION AND OVERFLOW OF PRECIPITATION.
- REMOVE AND DISPOSE OF HARDENED CONCRETE AND RETURN THE STRUCTURE TO A FUNCTIONAL CONDITION. CONCRETE MAY BE REUSED ONSITE OR HAULED AWAY FOR DISPOSAL OR RECYCLING.
- WHEN YOU REMOVE MATERIALS FROM THE SELF-INSTALLED CONCRETE WASHOUT, BUILD A NEW STRUCTURE; OR, IF THE PREVIOUS STRUCTURE IS STILL INTACT, INSPECT FOR SIGNS OF WEAKENING OR DAMAGE, AND MAKE ANY NECESSARY REPAIRS. RE-LINE THE STRUCTURE WITH NEW PLASTIC AFTER EACH CLEANING.

REMOVAL OF TEMPORARY CONCRETE WASHOUT FACILITIES


- WHEN TEMPORARY CONCRETE WASHOUT FACILITIES ARE NO LONGER REQUIRED FOR THE WORK, THE HARDENED CONCRETE, SLURRIES AND LIQUIDS SHALL BE REMOVED AND PROPERLY DISPOSED OF.
- MATERIALS USED TO CONSTRUCT TEMPORARY CONCRETE WASHOUT FACILITIES SHALL BE REMOVED FROM THE SITE OF THE WORK AND DISPOSED OF OR RECYCLED.
- HOLES, DEPRESSIONS OR OTHER GROUND DISTURBANCE CAUSED BY THE REMOVAL OF THE TEMPORARY CONCRETE WASHOUT FACILITIES SHALL BE BACKFILLED, REPAIRED, AND STABILIZED TO PREVENT EROSION.



EXCAVATED WASHOUT STRUCTURE



WASHOUT STRUCTURE WITH WOOD PLANKS



WASHOUT STRUCTURE WITH STRAW BALES

CONSTRUCTION SPECIFICATIONS


1. LOCATE WASHOUT STRUCTURE A MINIMUM OF 50 FEET AWAY FROM OPEN CHANNELS, STORM DRAIN INLETS, SENSITIVE AREAS, WETLANDS, BUFFERS AND WATER COURSES AND AWAY FROM CONSTRUCTION TRAFFIC.
2. SIZE WASHOUT STRUCTURE FOR VOLUME NECESSARY TO CONTAIN WASH WATER AND SOLIDS AND MAINTAIN AT LEAST 4 INCHES OF FREEBOARD. TYPICAL DIMENSIONS ARE 10 FEET X 10 FEET X 3 FEET DEEP.
3. PREPARE SOIL BASE FREE OF ROCKS OR OTHER DEBRIS THAT MAY CAUSE TEARS OR HOLES IN THE LINER. FOR LINER, USE 10 MIL OR THICKER UV RESISTANT, IMPERMEABLE SHEETING, FREE OF HOLES AND TEARS OR OTHER DEFECTS THAT COMPROMISE IMPERMEABILITY OF THE MATERIAL.
4. PROVIDE A SIGN FOR THE WASHOUT IN CLOSE PROXIMITY TO THE FACILITY.
5. KEEP CONCRETE WASHOUT STRUCTURE WATER TIGHT. REPLACE IMPERMEABLE LINER IF DAMAGED (E.G., RIPPED OR PUNCTURED). EMPTY OR REPLACE WASHOUT STRUCTURE THAT IS 75 PERCENT FULL, AND DISPOSE OF ACCUMULATED MATERIAL PROPERLY. DO NOT REUSE PLASTIC LINER. WET-VACUUM STORED LIQUIDS THAT HAVE NOT EVAPORATED AND DISPOSE OF IN AN APPROVED MANNER. PRIOR TO FORECASTED RAINSTORMS, REMOVE LIQUIDS OR COVER STRUCTURE TO PREVENT OVERFLOWS. REMOVE HARDENED SOLIDS, WHOLE OR BROKEN UP, FOR DISPOSAL OR RECYCLING. MAINTAIN RUNOFF DIVERSION AROUND EXCAVATED WASHOUT STRUCTURE UNTIL STRUCTURE IS REMOVED.

NOTE: WASHOUT OF THE CONCRETE TRUCK DRUM AT THE CONSTRUCTION SITE IS PROHIBITED

CONCRETE WASHDOWN AREA DETAIL

CSW

NOT TO SCALE



NOTES:

THE SEPARATION OF WATER MAINS AND SEWERS SHALL COMPLY WITH THE GEORGIA ENVIRONMENTAL PROTECTION DIVISION MINIMUM STANDARDS FOR PUBLIC WATER SYSTEMS, WHICH ARE GENERALLY AS FOLLOWS:

A. PARALLEL INSTALLATION:

1. NORMAL CONDITIONS: THE INSIDE EDGE OF A WATER LINE SHALL BE LAID AT LEAST 10 FEET HORIZONTALLY FROM THE INSIDE EDGE OF ANY SANITARY SEWER, STORM SEWER OR SEWER MANHOLE.
2. UNUSUAL CONDITIONS: WHEN LOCAL CONDITIONS PREVENT A HORIZONTAL SEPARATION OF 10 FEET, AND WHEN APPROVED BY THE ENGINEER, THE INSIDE EDGE OF A WATER MAIN MAY BE LAID A MINIMUM OF 5 FEET FROM THE INSIDE EDGE OF A SEWER PROVIDED THAT THE BOTTOM OF THE WATER MAIN IS AT LEAST 18 INCHES HIGHER THAN THE TOP OF THE SEWER (SEE DETAIL), AND THE WATER MAIN IS LAID IN A SEPARATE TRENCH OR ON AN UNDISTURBED EARTH SHELF.

B. CROSSINGS:

1. NORMAL CONDITIONS: WHENEVER POSSIBLE, THE BOTTOM OF THE WATER MAIN SHALL BE AT LEAST 18 INCHES HIGHER THAN THE TOP OF THE SEWER.
2. UNUSUAL CONDITIONS: IF A WATER MAIN MUST CROSS UNDER A SEWER, THE TOP OF THE WATER MAIN SHALL BE AT LEAST 18 INCHES LOWER THAN THE BOTTOM OF THE SEWER. THE WATER MAIN PIPE SHALL BE CENTERED AT THE CROSSING SO THAT THE JOINTS ARE EQUIDISTANT AND AS FAR AS POSSIBLE FROM THE SEWER, AND ADEQUATE STRUCTURAL SUPPORT SHALL BE PROVIDED FOR THE SEWER TO PREVENT EXCESSIVE DEFLECTION OF THE SEWER AT THE CROSSING. ADEQUATE STRUCTURAL SUPPORT SHALL INCLUDE BACKFILLING THE ENTIRE UTILITY CROSSING AREA WITH 3/4" CRUSHED STONE AS SHOWN IN THE DETAIL.

MINIMUM WATER & SEWER PIPE SEPARATION




City of Port Wentworth
TECHNICAL DETAILS

U-3

PREPARED BY SAUSSY ENGINEERING, LLC.

SCALE: N.T.S.
DATED: FEBRUARY 2007



CONTROL PANEL BACKBOARD




City of Port Wentworth
TECHNICAL DETAILS

S-11

PREPARED BY SAUSSY ENGINEERING, LLC.

SCALE: N.T.S.
DATED: FEBRUARY 2007



THIS DRAWING IS THE PROPERTY OF T. R. LONG ENGINEERING, P.C. AND MAY NOT BE REPRODUCED, COPIED, OR USED IN ANY MANNER WITHOUT THE WRITTEN PERMISSION OF T. R. LONG ENGINEERING, P.C.

THE CONTRACTOR SHALL VERIFY ALL DIMENSIONS CONTAINED WITHIN THIS SET OF DOCUMENTS AND SHALL REPORT ANY DISCREPANCIES TO T. R. LONG ENGINEERING, P.C. FOR IMMEDIATE RESOLUTION.

HINESVILLE:
114 North Commerce Street
Hinesville, Georgia 31313
(912) 368-5664

SAVANNAH:
308 Commercial Drive
Savannah, Georgia 31406
(912) 335-1046

TR LONG
ENGINEERING, P.C.

www.trlongeng.com

PINE FOREST
SEWER SYSTEM IMPROVEMENTS
CITY OF PORT WENTWORTH

SHEET NAME:
EROSION CONTROL
DETAILS

REVISIONS:

1.
2.
3.
4.
5.
6.
7.
8.
9.
10.

INITIAL DATE: 6/22/2022
DRAWN BY: KRC
CHECKED BY: TRL
PROJECT #: 2021-285

SHEET NUMBER:

C7.8

