

ADDENDUM NUMBER TWO  
TO  
REQUEST FOR BIDS, CONTRACT DOCUMENTS, CONSTRUCTION  
SPECIFICATIONS AND DRAWINGS  
FOR CONSTRUCTION OF

ROADWAY IMPROVEMENTS FOR LIVE OAK DRIVE  
FOR  
LIBERTY COUNTY BOARD OF COMMISSIONERS

ACKNOWLEDGE RECEIPT OF THIS ADDENDUM BY INSERTING ITS NUMBER IN THE PROPOSAL. FAILURE TO DO SO MAY SUBJECT BONA FIDE PROPOSERS TO DISQUALIFICATION. THIS ADDENDUM FORMS A PART OF THE PROJECT DOCUMENTS; IT MODIFIES THEM AS FOLLOWS:

BID DOCUMENTS:

1. The bid opening date has been changed to November 18, 2025 @ 10:00 A.M. Questions may be submitted no later than 5 business days before bid opening.

2. Question: Type A C.B.- the detail is showing a 4'X4' structure. Some of the structures can be made smaller, is this acceptable.

Response: The minimum inside dimension shall be 4'X4'.

3. Question: Pavement cross section calls for a 2' strip of sod on both sides. However, the plans only call for DS3. Please advise.

Response: The 2" strip of sod shall be removed, grassing will be through seeding.

4. Question: In what line item would you want to put the cost of the 6" concrete filler strip.

Response: The 6" filler strip has been added to the Schedule of Items. Please use the attached Schedule of Items.

5. Question: Plans call for a 10"X8" tapping sleeve with a valve box. However, the detail is showing that it will be in a manhole. Please advise.

Response: Please use a typical valve box.

6. Question: Will there be any tapping fees that the contractor will be responsible for.

Response: The contractor will not be responsible for any water impact of tapping fees.

7. Question: There is an underdrain detail, will there be any on this project.

Response: Underdrain has been added to the Schedule of Items. Please use the attached Schedule of Items.

8. Question: Is GDOT Contractor Prequal required to bid this project as a prime contractor?

Response: Prequalification by the Georgia Department of Transportation is not required.

SCHEDULE OF ITEMS  
LIVE OAK DRIVE  
IMPROVEMENTS  
TRL JOB #: 2024-141  
ADDENDUM #2

ITEM	DESCRIPTION	QUANTITY		COST	
		NUMBER OF UNITS	UNIT MEASURE	PER UNIT	TOTAL COST
1	GRADING MODIFIED	1	SUM		
2	ASPHALT MILLING	70	SY		
3	STRUCTURE RELOCATION	1	SUM		
4	1.5" 12.5mm ASPHALT OVERLAY (165 LB/SY)	700	TONS		
5	ASPHALT LEVEL COARSE (85 LB/SY)	700	TONS		
6	24" CURB AND GUTTER	5,450	LF		
7	6" FILLER STRIP	5,450	LF		
8	6" CONCRETE DRIVEWAY	2,000	SY		
9	5' SIDEWALK 4" THICK	3,040	SY		
10	HANDICAP RAMPS	6	EA		
11	PAVEMENT MARKINGS				
a	24" STOP BAR WHITE THERMOPLASTIC	4	EA		
b	6" DOUBLE YELLOW SOLID THERMOPLASTIC	2,700	LF		
c	8" CROSSWALK STRIP WHITE THERMOPLASTIC	1,000	LF		
d	RPM CENTERLINE YELLOW	150	EA		
e	RPM FIRE HYDRANT BLUE	4	EA		
12	R1-1 STOP SIGN W/POLE	3	EA		
13	15" FLARED END SECTION	2	EA.		
14	18" FLARED END SECTION	5	EA.		
15	30" FLARED END SECTION	1	EA.		
16	15" RCP DRAINAGE PIPE	600	LF		
17	18" RCP DRAINAGE PIPE	1,160	LF		

SCHEDULE OF ITEMS  
LIVE OAK DRIVE  
IMPROVEMENTS  
TRL JOB #: 2024-141  
ADDENDUM #2

ITEM	DESCRIPTION	QUANTITY		COST	
		NUMBER OF UNITS	UNIT MEASURE	PER UNIT	TOTAL COST
18	24" RCP DRAINAGE PIPE	840	LF		
19	30" RCP DRAINAGE PIPE	760	LF		
20	CURB INLET - TYPE A	23	EA		
21	CURB INLET - TYPE B	26	EA		
22	CURB INLET - TYPE C	15	EA		
23	JUNCTION BOX	3	EA		
24	INTERFERENCE BOX	6	EA		
25	UNDERDRAIN	4000	LF		
26	RAISE EXISTING MANHOLES TO GRADE	8	EA		
27	ROTATE EXISTING MANHOLE CONE/ RAISE LID TO GRADE	1	EA		
28	8" DIA. PVC WATER MAIN	1,700	LF		
29	FIRE HYDRANT ASSEMBLY	2	EA		
30	8" VALVE WITH VALVE BOX	6	EA		
31	6" VALVE WITH VALVE BOX	6	EA		
32	DUCTILE IRON FITTINGS	2.5	TONS		
33	CONNECT TO EXISTING WATER MAIN	12	EA		
34	WATER SERVICE ADJUSTMENTS	30	EA		
35	8"X1" SADDLE	30	EA		
36	1" WATER SERVICE LATERAL	500	LF		
37	HAYBALE CHECKDAMS (Cd-HB)	25	EA		
38	SILT FENCE (Sd2-NS)	5,300	LF		
39	TREE PROTECTION (Tr)	18	EA		

SCHEDULE OF ITEMS  
 LIVE OAK DRIVE  
 IMPROVEMENTS  
 TRL JOB #: 2024-141  
 ADDENDUM #2

ITEM	DESCRIPTION	QUANTITY		COST	
		NUMBER OF UNITS	UNIT MEASURE	PER UNIT	TOTAL COST
40	INLET PROTECTION (Sd2-F)	67	EA		
41	INLET PROTECTION (Sd2-P)	43	EA		
42	INLET PROTECTION (Sd2-S)	24	EA		
43	OUTLET PROTECTION (St)	120	SY		
44	ROCK DAM (Rd)	1	EA		
45	CONCRETE WASHOUT (CSW)	1	EA		
46	MULCHING Ds1	2.6	AC		
47	TEMPORARY GRASSING Ds2	2.6	AC		
48	PERMANENT GRASSING Ds3	2.57	AC		
49	TRAFFIC CONTROL	1	SUM		
50	MOBILIZATION (5%MAX)	1	SUM		
<b>GRAND TOTAL</b>					
<b>Grand Total in Words:</b>					